

RTL8139D RTL8139DL RTL8139D-LF RTL8139DL-LF RTL8139D-GR RTL8139DL-GR

## SINGLE-CHIP MULTI-FUNCTION 10/100Mbps ETHERNET CONTROLLER WITH POWER MANAGEMENT

#### **DATASHEET**

Rev. 1.2 08 Aug 2005

**Track ID: JATR-1076-21** 



#### Realtek Semiconductor Corp.

No. 2, Industry E. Rd. IX, Science-Based Industrial Park, Hsinchu 300, Taiwan Tel: +886-3-5780211 Fax: +886-3-5776047 www.realtek.com.tw



#### **COPYRIGHT**

©2005 Realtek Semiconductor Corp. All rights reserved. No part of this document may be reproduced, transmitted, transcribed, stored in a retrieval system, or translated into any language in any form or by any means without the written permission of Realtek Semiconductor Corp.

#### **DISCLAIMER**

Realtek provides this document "as is", without warranty of any kind, neither expressed nor implied, including, but not limited to, the particular purpose. Realtek may make improvements and/or changes in this document or in the product described in this document at any time. This document could include technical inaccuracies or typographical errors.

#### **TRADEMARKS**

Realtek is a trademark of Realtek Semiconductor Corporation. Other names mentioned in this document are trademarks/registered trademarks of their respective owners.

#### **USING THIS DOCUMENT**

Though every effort has been made to ensure that this document is current and accurate, more information may have become available subsequent to the production of this guide. In that event, please contact your Realtek representative for additional information that may help in the development process.

#### **REVISION HISTORY**

Revision	Release Date	Summary
1.2	2005/08/08	Added section 13 Ordering Information, on page 61.
		Added lead (Pb)-free and version package identification information on page 2 and page 3.



## **Table of Contents**

1. GEN	GENERAL DESCRIPTION1						
2. FEA	TURES	2					
3. PIN	ASSIGNMENTS	2					
3.1. 3.2.	PACKAGE IDENTIFICATIONPACKAGE IDENTIFICATION						
	DESCRIPTIONS						
4.1.	POWER MANAGEMENT/ISOLATION INTERFACE						
4.2.	PCI Interface						
4.3.	EEPROM INTERFACE						
4.4.	POWER PINS.						
4.5.	LED Interface						
4.6.	ATTACHMENT UNIT INTERFACE.						
4.7.	Multi-Function Interface						
4.8.	TEST AND OTHER PINS						
5. REC	GISTER DESCRIPTIONS	8					
5.1.	RECEIVE STATUS REGISTER IN RX PACKET HEADER	10					
5.2.	Transmit Status Register						
5.3.	ERSR: EARLY RX STATUS REGISTER						
5.4.	COMMAND REGISTER	12					
5.5.	Interrupt Mask Register	13					
5.6.	Interrupt Status Register	13					
5.7.	TRANSMIT CONFIGURATION REGISTER	14					
5.8.	RECEIVE CONFIGURATION REGISTER	15					
5.9.	9346CR: 93C46 COMMAND REGISTER	18					
5.10.	CONFIG 0: CONFIGURATION REGISTER 0	19					
5.11.	CONFIG 1: CONFIGURATION REGISTER 1	20					
5.12.	Media Status Register	21					
5.13.	CONFIG 3: CONFIGURATION REGISTER3	22					
5.14.	CONFIG 4: Configuration Register4	23					
5.15.	MULTIPLE INTERRUPT SELECT REGISTER	24					
5.16.	PCI REVISION ID	24					
5.17.	TRANSMIT STATUS OF ALL DESCRIPTORS (TSAD) REGISTER	24					
5.18.	BASIC MODE CONTROL REGISTER	25					
5.19.	BASIC MODE STATUS REGISTER						
5.20.	AUTO-NEGOTIATION ADVERTISEMENT REGISTER	26					
5.21.	AUTO-NEGOTIATION LINK PARTNER ABILITY REGISTER	27					
5.22.	AUTO-NEGOTIATION EXPANSION REGISTER	28					
5.23.	DISCONNECT COUNTER	28					

iii



5.24.	FALSE CARRIER SENSE COUNTER	28
5.25.	NWAY TEST REGISTER	
5.26.	RX ER COUNTER	29
5.27.	CS CONFIGURATION REGISTER.	29
5.28.	CONFIG5: CONFIGURATION REGISTER 5	30
6. EEPR	OM (93C46) CONTENTS	31
6.1.	SUMMARY OF RTL8139D(L) EEPROM REGISTERS	33
6.2.	SUMMARY OF EEPROM POWER MANAGEMENT REGISTERS	
7. PCI C	ONFIGURATION SPACE REGISTERS	34
7.1.	PCI CONFIGURATION SPACE TABLE	34
7.2.	PCI CONFIGURATION SPACE FUNCTIONS	
7.3.	DEFAULT VALUES AFTER POWER-ON (RSTB ASSERTED)	
7.4.	PCI POWER MANAGEMENT FUNCTIONS	
8. BLOC	K DIAGRAM	15
o. bloc	IX DIAGNAM	
9. FUNC	TIONAL DESCRIPTION	46
9.1.	TRANSMIT OPERATION	46
9.2.	RECEIVE OPERATION	46
9.3.	BASE LINE WANDER COMPENSATION	46
9.4.	Line Quality Monitor	
9.5.	CLOCK RECOVERY MODULE	
9.6.	LOOPBACK OPERATION	
9.7.	TX ENCAPSULATION	
9.8.	COLLISION	
9.9.	RX DECAPSULATION	
9.10.	FLOW CONTROL	
9.10.1.		
9.10.2.	1	
9.11.	LED FUNCTIONS.	
9.11.1.	1	
9.11.2. 9.11.3.	<del>-</del>	
9.11.3. 9.11.4.	<del>-</del>	
10.	APPLICATION DIAGRAM	51
11.	ELECTRICAL CHARACTERISTICS	52
11.1.	TEMPERATURE LIMIT RATINGS	52
11.2.	DC CHARACTERISTICS	
11.2.1.	11 7 0	
11.2.2.	11 7 8	
11.3.	AC CHARACTERISTICS	
11.3.1.	PCI Bus Operation Timing	53

iv



12.	MECHANICAL DIMENSIONS	59
12.1.	QFP	59
	LQFP	
13.	ORDERING INFORMATION	61



### 1. General Description

The Realtek RTL8139D(L) is a highly integrated and cost-effective single-chip Fast Ethernet controller that provides 32-bit performance, PCI bus master capability, and full compliance with IEEE 802.3u 100Base-T specifications and IEEE 802.3x Full Duplex Flow Control. It also supports Advanced Configuration Power management Interface (ACPI), PCI power management for modern operating systems that are capable of Operating System Directed Power Management (OSPM) to achieve the most efficient power management possible. The RTL8139D(L) also supports shared Boot ROM pins & clock run pin.

In addition to the ACPI feature, the RTL8139D(L) also supports remote wake-up (including AMD Magic Packet, LinkChg, and Microsoft® wake-up frame) in both ACPI and APM environments. The RTL8139D(L) is capable of performing an internal reset through the application of auxiliary power. When auxiliary power is applied and the main power remains off, the RTL8139D(L) is ready and is waiting for the Magic Packet or Link Change to wake the system up. Also, the LWAKE pin provides 4 different output signals including active high, active low, positive pulse, and negative pulse. The versatility of the RTL8139D(L) LWAKE pin provides motherboards with Wake-On-LAN (WOL) functionality.

The RTL8139D(L) also supports Analog Auto-Power-down, that is, the analog part of the RTL8139D(L) can be shut down temporarily according to user requirement or when the RTL8139D(L) is in a power down state with the wakeup function disabled. In addition, when the analog part is shut down and the IsolateB pin is low (i.e. the main power is off), then both the analog and digital parts stop functioning and the power consumption of the RTL8139D(L) will be negligible. The RTL8139D(L) also supports an auxiliary power auto-detect function, and will auto-configure related bits of their own PCI power management registers in PCI configuration space.

PCI Vital Product Data (VPD) is also supported to provide the information that uniquely identifies hardware (Ex., the OEM brand name of RTL8139D(L) LAN card). The information may consist of part number, serial number, and other detailed information.

To provide cost down support, the RTL8139D(L) is capable of using a 25MHz crystal or OSC as its internal clock source.

The RTL8139D(L) keeps network maintenance costs low and eliminates usage barriers. It is the easiest way to upgrade a network from 10 to 100Mbps. It also supports full-duplex operation, making 200Mbps bandwidth possible at no additional cost. To improve compatibility with other brands' products, the RTL8139D(L) is also capable of receiving packets with InterFrameGap no less than 40 Bit-Time. The RTL8139D(L) is highly integrated and requires no "glue" logic or external memory.

The RTL8139D(L) provides a flexible multi-function mode (Realtek patent pending) to incorporate other PCI master devices, like a hardware modem. When in multi-function mode, the RTL8139D(L) acts as an arbiter to distinguish LAN signals from those of other devices. The second device recognizes no difference between being connected to the RTL8139D or a regular PCI bus.

The RTL8139D(L) includes a PCI and Expansion Memory Share Interface (Realtek's patent pending) for a boot ROM and can be used in diskless workstations, providing maximum network security and ease of management.



#### 2. Features

- 100 pin QFP/LQFP
- Integrated Fast Ethernet MAC, Physical chip and transceiver in one chip
- 10Mbps and 100Mbps operation
- Supports 10Mbps and 100Mbps N-way Auto-negotiation operation
- Supports PCI multi-function capabilities
- PCI local bus single-chip Fast Ethernet controller
  - ◆ Complies with PCI Revision 2.2
  - ◆ Supports PCI clock 16.75MHz-40MHz
  - Supports PCI target fast back-to-back transaction
  - Provides PCI bus master data transfers and PCI memory space or I/O space mapped data transfers of RTL8139D(L)'s operational registers
  - Supports PCI VPD (Vital Product Data)
  - Supports ACPI, PCI power management
  - Supports PCI multi-function to incorporate with other PCI master device
  - ◆ Supports 25MHz crystal or 25MHz OSC as the internal clock source. The frequency deviation of either crystal or OSC must be within 50 PPM.
- Complies with PC99 and PC2001 standards
- Supports Wake-On-LAN function and remote wake-up (Magic Packet\*, LinkChg and Microsoft® wake-up frame)

- Supports 4 Wake-On-LAN (WOL) signals (active high, active low, positive pulse, and negative pulse)
- Supports auxiliary power-on internal reset, to be ready for remote wake-up when main power remains off
- Supports auxiliary power auto-detect, and sets the related capability of power management registers in PCI configuration space
- Includes a programmable, PCI burst size and early Tx/Rx threshold
- Supports a 32-bit general-purpose timer with the external PCI clock as clock source, to generate timer-interrupt
- Contains two large (2Kbyte) independent receive and transmit FIFO's
- Advanced power saving mode when LAN function or wakeup function is not used
- Uses 93C46 (64\*16-bit EEPROM) to store resource configuration, ID parameter, and VPD data
- Supports LED pins for various network activity indications
- Supports loopback capability
- Half/Full duplex capability
- Supports Full Duplex Flow Control (IEEE 802.3x)
- 2.5/3.3V power supply with 5V tolerant I/Os
- Up to 128K byte Boot ROM interface for both EPROM and Flash memory is supported
- 0.25u CMOS process



### 3. Pin Assignments




Figure 1. Pin Assignments (100-Pin QFP)

### 3.1. Package Identification

Lead (Pb)-free package is indicated by an 'L' in the location marked 'T' in Figure 1.

'Green' package is indicated by a 'G' in the location marked 'T' in Figure 1.






Figure 2. Pin Assignments (100-Pin LQFP)

### 3.2. Package Identification

Lead (Pb)-free package is indicated by an 'L' in the location marked 'T' in Figure 2.

'Green' package is indicated by a 'G' in the location marked 'T' in Figure 2.



## 4. Pin Descriptions

Note that some pins have multiple functions. Refer to the Pin Assignment diagrams for a graphical representation.

### 4.1. Power Management/Isolation Interface

Symbol	Type	Pin No	Description
PMEB (PME#)	O/D	57	<b>Power Management Event:</b> Open drain, active low. Used by the RTL8139D(L) to request a change in its current power management state and/or to indicate that a power management event has occurred.
ISOLATEB (ISOLATE#)	I	74	<b>Isolate pin:</b> Active low. Used to isolate the RTL8139D(L) from the PCI bus. The RTL8139D(L) does not drive its PCI outputs (excluding PME#) and does not sample its PCI input (including RST# and PCICLK) as long as the Isolate pin is asserted.
LWAKE	O	64	LAN WAKE-UP signal: This signal is used to inform the motherboard to execute the wake-up process. The motherboard must support Wake-On-LAN (WOL). There are 4 choices of output, including active high, active low, positive pulse, and negative pulse, that may be asserted from the LWAKE pin. Please refer to the LWACT bit in the CONFIG1 register and the LWPTN bit in the CONFIG4 register for the setting of this output signal. The default output is an active high signal. Once a PME event is received, the LWAKE and PMEB assert at the same time when the LWPME (bit4, CONFIG4) is set to 0. If the LWPME is set to 1, the LWAKE asserts only when the PMEB asserts and the ISOLATEB is low. This pin is a 3.3V signaling output pin.

#### 4.2. PCI Interface

Type	Pin No	Description
T/S	86,87,89,91-95,100,	PCI address and data multiplexed pins.
	1,3-5,8-10,23-30,33,	Pins AD31-24 are shared with BootROM data pins, while AD16-0 are
	36-38,41,42,44,45	shared with BootROM address pins.
T/S	98,11,21,32	PCI bus command and byte enables multiplexed pins.
I	83	Clock: This PCI Bus clock provides timing for all transactions and bus
		phases, and is input to PCI devices. The rising edge defines the start of
		each phase. The clock frequency ranges from 0 to 33MHz.
S/T/S	15	<b>Device Select:</b> As a bus master, the RTL8139D(L) samples this signal
		to insure that a PCI target recognizes the destination address for the data
		transfer. As a target, the RTL8139D(L) asserts this signal low when it
		recognizes its target address after FRAMEB is asserted.
S/T/S	12	Cycle Frame: As a bus master, this pin indicates the beginning and
		duration of an access. FRAMEB is asserted low to indicate the start of a
		bus transaction. While FRAMEB is asserted, data transfer continues.
		When FRAMEB is deasserted, the transaction is in the final data phase.
		As a target, the device monitors this signal before decoding the address
		to check if the current transaction is addressed to it.
	T/S  T/S  I  S/T/S	T/S 86,87,89,91-95,100, 1,3-5,8-10,23-30,33, 36-38,41,42,44,45  T/S 98,11,21,32  I 83  S/T/S 15



Symbol	Type	Pin No	Description
GNTB	I	84	<b>Grant:</b> This signal is asserted low to indicate to the RTL8139D(L) that the central arbiter has granted ownership of the bus to the RTL8139D(L). This input is used when the RTL8139D(L) is acting as a bus master.
REQB	T/S	85	<b>Request:</b> The RTL8139D(L) will assert this signal low to request the ownership of the bus from the central arbiter.
IDSEL	I	99	<b>Initialization Device Select</b> : This pin allows the RTL8139D(L) to identify when configuration read/write transactions are intended for it.
INTAB	O/D	81	<b>INTAB:</b> Used to request an interrupt. It is asserted low when an interrupt condition occurs, as defined by the Interrupt Status, Interrupt Mask and Interrupt Enable registers.
IRDYB	S/T/S	13	<b>Initiator Ready</b> : This indicates the initiating agent's ability to complete the current data phase of the transaction.
			As a bus master, this signal will be asserted low when the RTL8139D(L) is ready to complete the current data phase transaction. This signal is used in conjunction with the TRDYB signal. Data transaction takes place at the rising edge of CLK when both IRDYB and TRDYB are asserted low. As a target, this signal indicates that the master has put data on the bus.
TRDYB	S/T/S	14	<b>Target Ready:</b> This indicates the target agent's ability to complete the current phase of the transaction.
			As a bus master, this signal indicates that the target is ready for the data during write operations and with the data during read operations. As a target, this signal will be asserted low when the (slave) device is ready to complete the current data phase transaction. This signal is used in conjunction with the IRDYB signal. Data transaction takes place at the rising edge of CLK when both IRDYB and TRDYB are asserted low.
PAR	T/S	20	<b>Parity:</b> This signal indicates even parity across AD31-0 and C/BE3-0 including the PAR pin. As a master, PAR is asserted during address and write data phases. As a target, PAR is asserted during read data phases.
PERRB	S/T/S	18	Parity Error: When the RTL8139D(L) is the bus master and a parity error is detected, the RTL8139D(L) asserts both SERR bit in ISR and Configuration Space command bit 8 (SERRB enable). Next, it completes the current data burst transaction, then stops operation and resets itself. After the host clears the system error, the RTL8139D(L) continues its operation.
			When the RTL8139D(L) is the bus target and a parity error is detected, the RTL8139D(L) asserts this PERRB pin low.
SERRB	O/D	19	<b>System Error:</b> If an address parity error is detected and Configuration Space Status register bit 15 (detected parity error) is enabled, RTL8139D(L) asserts both SERRB pin low and bit 14 of Status register in Configuration Space.
STOPB	S/T/S	17	<b>Stop:</b> Indicates the current target is requesting the master to stop the current transaction.
RSTB	I	82	<b>Reset:</b> When RSTB is asserted low, the RTL8139D(L) performs internal system hardware reset. RSTB must be held for a minimum of 120 ns.



### 4.3. EEPROM Interface

Symbol	Type	Pin No	Description
AUX	I	50	Aux. Power Detect: This pin is used to notify the RTL8139D(L) of the existence of Aux. power during initial power-on or a PCI reset.  This pin should be pulled high to the Aux. power via a resistor to detect the Aux. power. Doing so, will enable wakeup support from ACPI D3 cold or APM power-down. If this pin is not pulled high, the RTL8139D(L) assumes that no Aux. power exists.
EESK	О	48	The MA2-0 pins are switched to EESK, EEDI, EEDO in 93C46
EEDI	О	47	programming or auto-load mode.
EEDO	O, I	46	
EECS	О	49	EEPROM chip select

### 4.4. Power Pins

Symbol	Type	Pin No	Description
VDD	P	6,22,34,39,90,97	+3.3V (Digital)
AVDD	P	59,70,75	+3.3V (Analog)
VDD25	P	51,96	+2.5V (Digital)
AVDD25	P	58	+2.5V (Analog)
GND	P	2,16,31,43,56,	Ground
		62,66,73,88	

#### 4.5. LED Interface

Symbol	Type	Pin No		]	Description		
LED0, 1, 2	О	80,79,77	LED pins				
			LEDS1-0	00	01	10	11
			LED0	TX/RX	TX/RX	TX	TX
			LED1	LINK100	LINK10/100	LINK10/100	LINK100
			LED2	LINK10	FULL	RX	LINK10
			During power de	own mode, the	e LED's are C	FF.	



#### 4.6. Attachment Unit Interface

Symbol	Type	Pin No	Description
TXD+	О	72	100/10BASE-T transmit (Tx) data.
TXD-	O	71	
RXIN+	I	68	100/10BASE-T receive (Rx) data.
RXIN-	I	67	
X1	I	61	25 MHz crystal/OSC. input.
X2	О	60	Crystal feedback output: This output is used in crystal connection only.
			It must be left open when X1 is driven with an external 25 MHz oscillator.

#### 4.7. Multi-Function Interface

Symbol	Type	Pin No	Description
REQB2	IN	53	<b>Request2:</b> The 2 <sup>nd</sup> device will assert this pin low to request the
			ownership of the PCI bus.
GNTB2	T/S,O	54	<b>Grant2:</b> This signal is asserted low to indicate that the central arbiter
			has granted ownership of the bus to the 2 <sup>nd</sup> device.
IDSEL2	0	78	Initialization Device Select 2: Used as a chip-select during
			configuration read and write transactions to the 2 <sup>nd</sup> device.

#### 4.8. Test And Other Pins

Symbol	Type	Pin No	Description					
RTT3	TEST	63	Chip test pin.					
RTSET	I/O	65	This pin must be pulled low by a resistor. Please refer to the application circuit for correct value.					
VCTRL	Analog	55	Use this pin and an external PNP type transistor to generate +2.5V for the RTL8139D(L).					
ROMCS/OEB	О	35	<b>ROM Chip Select and Output Enable:</b> This is the chip select signal and output enable for the Boot PROM.					
CLKRUNB	I/O	52	Clock Run: This signal is used by the RTL8139D(L) to request starting (or speeding up) the clock, CLK. CLKRUNB also indicates the clock status. For the RTL8139D(L), CLKRUNB is an open drain output as well as an input. The RTL8139D(L) requests the central resource to start, speed up, or maintain the interface clock by the assertion of CLKRUNB. For the host system, it is an S/T/S signal. The host system (central resource) is responsible for maintaining CLKRUNB asserted, and for driving it high to the negated (deasserted) state.					
NC	-	7,40,69,76	Reserved					



## 5. Register Descriptions

The RTL8139D(L) provides the following set of operational registers mapped into PCI memory space or I/O space.

Offset	R/W	Tag	Description					
0000h	R/W	IDR0	ID Register 0, The ID register0-5 are only permitted to read/write by					
			4-byte access. Read access can be byte, word, or double word access.					
			The initial value is autoloaded from EEPROM EthernetID field.					
0001h	R/W	IDR1	ID Register 1					
0002h	R/W	IDR2	ID Register 2					
0003h	R/W	IDR3	ID Register 3					
0004h	R/W	IDR4	ID Register 4					
0005h	R/W	IDR5	ID Register 5					
0006h-0007h	-	-	Reserved					
0008h	R/W	MAR0	Multicast Register 0, The MAR register 0-7 are only permitted to					
			read/write by 4-byte access. Read access can be byte, word, or double					
			word access. Driver is responsible for initializing these registers.					
0009h	R/W	MAR1	Multicast Register 1					
000Ah	R/W	MAR2	Multicast Register 2					
000Bh	R/W	MAR3	Multicast Register 3					
000Ch	R/W	MAR4	Multicast Register 4					
000Dh	R/W	MAR5	Multicast Register 5					
000Eh	R/W	MAR6	Multicast Register 6					
000Fh	R/W	MAR7	Multicast Register 7					
0010h-0013h	R/W	TSD0	Transmit Status of Descriptor 0					
0014h-0017h	R/W	TSD1	Transmit Status of Descriptor 1					
0018h-001Bh	R/W	TSD2	Transmit Status of Descriptor 2					
001Ch-001Fh	R/W	TSD3	Transmit Status of Descriptor 3					
0020h-0023h	R/W	TSAD0	Transmit Start Address of Descriptor0					
0024h-0027h	R/W	TSAD1	Transmit Start Address of Descriptor1					
0028h-002Bh	R/W	TSAD2	Transmit Start Address of Descriptor2					
002Ch-002Fh	R/W	TSAD3	Transmit Start Address of Descriptor3					
0030h-0033h	R/W	RBSTART	Receive (Rx) Buffer Start Address					
0034h-0035h	R	ERBCR	Early Receive (Rx) Byte Count Register					
0036h	R	ERSR	Early Rx Status Register					
0037h	R/W	CR	Command Register					
0038h-0039h	R/W	CAPR	Current Address of Packet Read					
003Ah-003Bh	R	CBR	Current Buffer Address: The initial value is 0000h. It reflects total					
			received byte-count in the rx buffer.					
003Ch-003Dh	R/W	IMR	Interrupt Mask Register					
003Eh-003Fh	R/W	ISR	Interrupt Status Register					
0040h-0043h	R/W	TCR	Transmit (Tx) Configuration Register					
0044h-0047h	R/W	RCR	Receive (Rx) Configuration Register					
0048h-004Bh	R/W	TCTR	Timer CounT Register: This register contains a 32-bit general-purpose					
			timer. Writing any value to this 32-bit register will reset the original					
00461 0045	D /337	1.000	timer and begin to count from zero.					
004Ch-004Fh	R/W	MPC	Missed Packet Counter: Indicates the number of packets discarded due					
			to Rx FIFO overflow. It is a 24-bit counter. After s/w reset, MPC is					
	1		cleared. Only the lower 3 bytes are valid.					



Offset	R/W	Tag	Description			
			When written any value, MPC will be reset also.			
0050h	R/W	9346CR	93C46 Command Register			
0051h	R/W	CONFIG0	Configuration Register 0			
0052h	R/W	CONFIG1	Configuration Register 1			
0053H	-	-	Reserved			
0054h-0057h	R/W	TimerInt	Timer Interrupt Register. Once having written a nonzero value to this register, the Timeout bit of ISR register will be set whenever the			
			TCTR reaches to this value. The Timeout bit will never be set as long as TimerInt register is zero.			
0058h	R/W	MSR	Media Status Register			
0059h	R/W	CONFIG3	Configuration register 3			
005Ah	R/W	CONFIG4	Configuration register 4			
005Bh	-	-	Reserved			
005Ch-005Dh	R/W	MULINT	Multiple Interrupt Select			
005Eh	R	RERID	PCI Revision ID = 10h.			
005Fh	-	-	Reserved.			
0060h-0061h	R	TSAD	Transmit Status of All Descriptors			
0062h-0063h	R/W	BMCR	Basic Mode Control Register			
0064h-0065h	R	BMSR	Basic Mode Status Register			
0066h-0067h	R/W	ANAR	Auto-Negotiation Advertisement Register			
0068h-0069h	R	ANLPAR	Auto-Negotiation Link Partner Register			
006Ah-006Bh	R	ANER	Auto-Negotiation Expansion Register			
006Ch-006Dh	R	DIS	Disconnect Counter			
006Eh-006Fh	R	FCSC	False Carrier Sense Counter			
0070h-0071h	R/W	NWAYTR	N-way Test Register			
0072h-0073h	R	REC	RX_ER Counter			
0074h-0075h	R/W	CSCR	CS Configuration Register			
0076-0077h	-	-	Reserved.			
0078h-007Bh	R/W	PHY1_PARM	PHY parameter 1			
007Ch-007Fh	R/W	TW_PARM	Twister parameter			
0080h	R/W	PHY2_PARM	PHY parameter 2			
0081-0083h	-	-	Reserved			
0084h	R/W	CRC0	Power Management CRC register0 for wakeup frame0			
0085h	R/W	CRC1	Power Management CRC register1 for wakeup frame1			
0086h	R/W	CRC2	Power Management CRC register2 for wakeup frame2			
0087h	R/W	CRC3	Power Management CRC register3 for wakeup frame3			
0088h	R/W	CRC4	Power Management CRC register4 for wakeup frame4			
0089h	R/W	CRC5	Power Management CRC register5 for wakeup frame5			
008Ah	R/W	CRC6	Power Management CRC register6 for wakeup frame6			
008Bh	R/W	CRC7	Power Management CRC register7 for wakeup frame7			
008Ch-0093h	R/W	Wakeup0	Power Management wakeup frame0 (64bit)			
0094h-009Bh	R/W	Wakeup1	Power Management wakeup frame1 (64bit)			
009Ch-00A3h	R/W	Wakeup2	Power Management wakeup frame2 (64bit)			
00A4h-00ABh	R/W	Wakeup3	Power Management wakeup frame3 (64bit)			
00ACh-00B3h	R/W	Wakeup4	Power Management wakeup frame4 (64bit)			
00B4h-00BBh	R/W	Wakeup5	Power Management wakeup frame 5 (64bit)			
00BCh-00C3h	R/W	Wakeup6	Power Management wakeup frame6 (64bit)			
00C4h-00CBh	R/W	Wakeup7	Power Management wakeup frame7 (64bit)			
00CCh	R/W	LSBCRC0	LSB of the mask byte of wakeup frame0 within offset 12 to 75			



Offset	R/W	Tag	Description
00CDh	R/W	LSBCRC1	LSB of the mask byte of wakeup frame1 within offset 12 to 75
00CEh	R/W	LSBCRC2	LSB of the mask byte of wakeup frame2 within offset 12 to 75
00CFh	R/W	LSBCRC3	LSB of the mask byte of wakeup frame3 within offset 12 to 75
00D0h	R/W	LSBCRC4	LSB of the mask byte of wakeup frame4 within offset 12 to 75
00D1h	R/W	LSBCRC5	LSB of the mask byte of wakeup frame5 within offset 12 to 75
00D2h	R/W	LSBCRC6	LSB of the mask byte of wakeup frame6 within offset 12 to 75
00D3h	R/W	LSBCRC7	LSB of the mask byte of wakeup frame7 within offset 12 to 75
00D4h-00D7h	-	-	Reserved.
00D8h	R/W	Config5	Configuration register 5
00D9h-00FFh	-	-	Reserved.

## 5.1. Receive Status Register in Rx Packet Header

Bit	R/W	Symbol	Description
15	R	MAR	<b>Multicast Address Received:</b> This bit set to 1 indicates that a multicast packet is received.
14	R	PAM	<b>Physical Address Matched:</b> This bit set to 1 indicates that the destination address of this packet matches the value written in ID registers.
13	R	BAR	<b>Broadcast Address Received:</b> This bit set to 1 indicates that a broadcast packet is received. BAR, MAR bit will not be set simultaneously.
12-6	-	-	Reserved
5	R	ISE	<b>Invalid Symbol Error:</b> (100BASE-TX only) This bit set to 1 indicates that an invalid symbol was encountered during the reception of this packet.
4	R	RUNT	<b>Runt Packet Received:</b> This bit set to 1 indicates that the received packet length is smaller than 64 bytes (i.e. media header + data + CRC < 64 bytes)
3	R	LONG	<b>Long Packet:</b> This bit set to 1 indicates that the size of the received packet exceeds 4k bytes.
2	R	CRC	<b>CRC Error:</b> When set, indicates that a CRC error occurred on the received packet.
1	R	FAE	<b>Frame Alignment Error:</b> When set, indicates that a frame alignment error occurred on this received packet.
0	R	ROK	<b>Receive OK:</b> When set, indicates that a good packet is received.



## 5.2. Transmit Status Register

### (TSD0-3)(Offset 0010h-001Fh, R/W)

The read-only bits (CRS, TABT, OWC, CDH, NCC3-0, TOK, TUN) will be cleared by the RTL8139D(L) when the Transmit Byte Count (bits 12-0) in the corresponding Tx descriptor is written. It is not affected when software writes to these bits. These registers are only permitted to write by double-word access. After software reset, all bits except OWN bit are reset to "0".

Bit	R/W	Symbol	Description				
31	R	CRS	<b>Carrier Sense Lost:</b> This bit is set to 1 when the carrier is lost during				
			transmission of a packet.				
30	R	TABT	<b>Transmit Abort:</b> This bit is set to 1 if the transmission of a packet was aborted. This bit is read only, writing to this bit is not affected.				
29	R	OWC	<b>Out of Window Collision:</b> This bit is set to 1 if the RTL8139D(L) encountered an "out of window" collision during the transmission of a packet.				
28	R	CDH	<b>CD Heart Beat:</b> The NIC watches for a collision signal (ie, CD Heartbeat signal) during the first 6.4us of the interframe gap following a transmission. This bit is set if the transceiver fails to send this signal. This bit is cleared in the 100 Mbps mode.				
27-24	R	NCC3-0	<b>Number of Collision Count:</b> Indicates the number of collisions encountered during the transmission of a packet.				
23-22	-	-	Reserved				
21-16	R/W	ERTXTH5-0	Early Tx Threshold: Specifies the threshold level in the Tx FIFO to begin the transmission. When the byte count of the data in the Tx FIFO reaches this level, (or the FIFO contains at least one complete packet) the RTL8139D(L) will transmit this packet.  000000 = 8 bytes  These fields count from 000001 to 111111 in unit of 32 bytes.  This threshold must avoid exceeding 2K bytes.				
15	R	TOK	<b>Transmit OK:</b> Set to 1 indicates that the transmission of a packet was completed successfully and no transmit underrun has occurred.				
14	R	TUN	<b>Transmit FIFO Underrun:</b> Set to 1 if the Tx FIFO was exhausted during the transmission of a packet. The RTL8139D(L) can re-transfer data if the Tx FIFO underruns and can also transmit the packet to the wire successfully even though the Tx FIFO underruns. That is, when TSD <tun>=1, TSD<tok>=0 and ISR<tok>=1 (or ISR<ter>=1).</ter></tok></tok></tun>				
13	R/W	OWN	<b>OWN:</b> The RTL8139D(L) sets this bit to 1 when the Tx DMA operation of this descriptor was completed. The driver must set this bit to 0 when the Transmit Byte Count (bits 0-12) is written. The default value is 1.				
12-0	R/W	SIZE	<b>Descriptor Size:</b> The total size in bytes of the data in this descriptor. If the packet length is more than 1792 byte (0700h), the Tx queue will be invalid, i.e. the next descriptor will be written only after the OWN bit of that long packet's descriptor has been set.				

11



## 5.3. ERSR: Early Rx Status Register

(Offset 0036h, R)

Bit	R/W	Symbol	Description
7-4	-	-	Reserved
3	R	ERGood	Early Rx Good packet: This bit is set whenever a packet is completely
			received and the packet is good. Writing a 1 to this bit will clear it.
2	R	ERBad	Early Rx Bad packet: This bit is set whenever a packet is completely
			received and the packet is bad. Writing a 1 to this bit will clear it.
1	R	EROVW	Early Rx OverWrite: This bit is set when the RTL8139D(L)'s local
			address pointer is equal to CAPR. In the early mode, this is different
			from buffer overflow. It happens that the RTL8139D(L) detected an Rx
			error and wanted to fill another packet data from the beginning address
			of that error packet. Writing a 1 to this bit will clear it.
0	R	EROK	Early Rx OK: The power-on value is 0. It is set when the Rx byte count
			of the arriving packet exceeds the Rx threshold. After the whole packet
			is received, the RTL8139D(L) will set ROK or RER in ISR and clear
			this bit simultaneously. Setting this bit will invoke a ROK interrupt.

## 5.4. Command Register

(Offset 0037h, R/W)

This register is used for issuing commands to the RTL8139D(L). These commands are issued by setting the corresponding bits for the function. A global software reset along with individual reset and enable/disable for transmitter and receiver are provided here.

Bit	R/W	Symbol	Description
7-5	-	-	Reserved
4	R/W	RST	<b>Reset:</b> Setting to 1 forces the RTL8139D(L) to a software reset state which disables the transmitter and receiver, reinitializes the FIFOs, resets the system buffer pointer to the initial value (Tx buffer is at TSAD0, Rx buffer is empty). The values of IDR0-5 and MAR0-7 and PCI configuration space will have no changes. This bit is 1 during the reset operation, and is cleared to 0 by the RTL8139D(L) when the reset operation is complete.
3	R/W	RE	Receiver Enable: When set to 1, and the receive state machine is idle, the receive machine becomes active. This bit will read back as a 1 whenever the receive state machine is active. After initial power-up, software must insure that the receiver has completely reset before setting this bit.
2	R/W	TE	<b>Transmitter Enable:</b> When set to 1, and the transmit state machine is idle, then the transmit state machine becomes active. This bit will read back as a 1 whenever the transmit state machine is active. After initial power-up, software must insure that the transmitter has completely reset before setting this bit.
1	-	-	Reserved
0	R	BUFE	<b>Buffer Empty:</b> Rx Buffer Empty. There is no packet stored in the Rx buffer ring.



## 5.5. Interrupt Mask Register (Offset 003Ch-003Dh, R/W)

This register masks the interrupts that can be generated from the Interrupt Status Register. A hardware reset will clear all mask bits. Setting a mask bit allows the corresponding bit in the Interrupt Status Register to cause an interrupt. The Interrupt Status Register bits are always set to 1 if the condition is present, regardless of the state of the corresponding mask bit.

Bit	R/W	Symbol	Description					
15	R/W	SERR	<b>System Error Interrupt:</b> 1 => Enable, 0 => Disable.					
14	R/W	TimeOut	<b>Time Out Interrupt:</b> 1 => Enable, 0 => Disable.					
13	R/W	LenChg	<b>Cable Length Change Interrupt:</b> 1 => Enable, 0 => Disable.					
12-7	ı	-	Reserved					
6	R/W	FOVW	<b>Rx FIFO Overflow Interrupt:</b> 1 => Enable, 0 => Disable.					
5	R/W	PUN/LinkChg	Packet Underrun/Link Change Interrupt: 1 => Enable, 0 =>					
			Disable.					
4	R/W	RXOVW	<b>Rx Buffer Overflow Interrupt:</b> 1 => Enable, 0 => Disable.					
3	R/W	TER	<b>Transmit Error Interrupt:</b> 1 => Enable, 0 => Disable.					
2	R/W	TOK	<b>Transmit OK Interrupt:</b> 1 => Enable, 0 => Disable.					
1	R/W	RER	<b>Receive Error Interrupt:</b> 1 => Enable, 0 => Disable.					
0	R/W	ROK	<b>Receive OK Interrupt:</b> 1 => Enable, 0 => Disable.					

# 5.6. Interrupt Status Register (Offset 003Eh-003Fh, R/W)

This register indicates the source of an interrupt when the INTA pin goes active. Enabling the corresponding bits in the Interrupt Mask Register (IMR) allows bits in this register to produce an interrupt. When an interrupt is active, one of more bits in this register are set to a "1". The interrupt Status Register reflects all current pending interrupts, regardless of the state of the corresponding mask bit in the IMR. Reading the ISR clears all interrupts. Writing to the ISR has no effect.

Bit	R/W	Symbol	Description
15	R/W	SERR	<b>System Error:</b> Set to 1 when the RTL8139D(L) signals a system error on the PCI bus.
14	R/W	TimeOut	<b>Time Out:</b> Set to 1 when the TCTR register reaches to the value of the TimerInt register.
13	R/W	LenChg	Cable Length Change: Cable length is changed after Receiver is enabled.
12 - 7	-	-	Reserved
6	R/W	FOVW	<b>Rx FIFO Overflow:</b> Set when an overflow occurs on the Rx status FIFO.
5	R/W	PUN/LinkChg	<b>Packet Underrun/Link Change:</b> Set to 1 when CAPR is written but Rx buffer is empty, or when link status is changed.
4	R/W	RXOVW	<b>Rx Buffer Overflow:</b> Set when receive (Rx) buffer ring storage resources have been exhausted.
3	R/W	TER	<b>Transmit (Tx) Error:</b> Indicates that a packet transmission was aborted, due to excessive collisions, according to the TXRR's setting.
2	R/W	TOK	<b>Transmit (Tx) OK:</b> Indicates that a packet transmission is completed successfully.
1	R/W	RER	Receive (Rx) Error: Indicates that a packet has either CRC error or



Bit	R/W	Symbol	Description					
			frame alignment error (FAE). The collided frame will not be recognized					
			as CRC error if the length of this frame is shorter than 16 byte.					
0	R/W	ROK	Receive (Rx) OK: In normal mode, indicates the successful completion					
			of a packet reception. In early mode, indicates that the Rx byte count of					
			the arriving packet exceeds the early Rx threshold.					

# 5.7. Transmit Configuration Register (Offset 0040h-0043h, R/W)

This register defines the Transmit Configuration for the RTL8139D(L). It controls such functions as Loopback, Heartbeat, Auto Transmit Padding, programmable Interframe Gap, Fill and Drain Thresholds, and maximum DMA burst size.

Bit	R/W	Symbol	Description							
31	=	-	Reserved							
30-26	R	HWVERID_A	Hardware Version ID A:							
		_		Bit30	Bit29	Bit28	Bit27	Bit26	Bit23	Bit22
			RTL8139	1	1	0	0	0	0	0
			RTL8139A	1	1	1	0	0	0	0
			RTL8139A-G	1	1	1	0	1	0	0
			RTL8139B	1	1	1	1	0	0	0
			RTL8130	1	1	1	1	0	0	0
			RTL8139C	1	1	1	0	1	0	0
			RTL8100	1	1	1	1	0	1	0
			RTL8100B/	1	1	1	0	1	0	1
			8139D							
			RTL8139C+	1	1	1	0	1	1	0
			RTL8101	1	1	1	0	1	1	1
			Reserved			Other	combin	nation		
	- /	TTG1 0			ent :	~				
25-24	R/W	IFG1, 0	Interframe Ga							
			interframe gap ti							
			100Mbps. The time							
			and 960ns to 840 will violate the I				nat any	value (	omer ma	m (1, 1)
			The formula for							
			10 Mbps	tiic iiitei	maine ;		s + 0.40	IFG(1:0	))) 116	
			100 Mbps				,	IFG(1:0	//	
23-22	R	HWVERID B	Hardware Vers	ion ID 1	B	3.01		. =(1.0	,,,	
21-19	-	<del>-</del>	Reserved							
18, 17	R/W	LBK1, LBK0	Loopback test:	There w	vill be n	o packe	et on th	e TX+/-	- lines ı	ınder the
ĺ		, ,								
			Loopback test condition. The loopback function must be independent of the link state.							
			00 : normal operation							
			01 : Reserved							
			10 : Reserved							
			11 : Loopback m	ode						



Bit	R/W	Symbol	Description
16	R/W	CRC	<b>Append CRC:</b> Setting to 1 means that there is no CRC appended at the end of a packet. Setting to 0 means that there is CRC appended at the end of a packet.
15-11	-	-	Reserved
10-8	R/W	MXDMA2, 1, 0	Max DMA Burst Size per Tx DMA Burst: This field sets the maximum size of transmit DMA data bursts according to the following table:  000 = 16 bytes  001 = 32 bytes  010 = 64 bytes  011 = 128 bytes  100 = 256 bytes  101 = 512 bytes  110 = 1024 bytes  111 = 2048 bytes
7-4	R/W	TXRR	Tx Retry Count: These are used to specify additional transmission retries in multiple of 16(IEEE 802.3 CSMA/CD retry count). If the TXRR is set to 0, the transmitter will re-transmit 16 times before aborting due to excessive collisions. If the TXRR is set to a value greater than 0, the transmitter will re-transmit a number of times equals to the following formula before aborting:  Total retries = 16 + (TXRR * 16)  The TER bit in the ISR register or transmit descriptor will be set when the transmission fails and reaches to this specified retry count.
3-1	-	-	Reserved
0	W	CLRABT	<b>Clear Abort:</b> Setting this bit to 1 causes the RTL8139D(L) to retransmit the packet at the last transmitted descriptor when this transmission was aborted, Setting this bit is only permitted in the transmit abort state.

# 5.8. Receive Configuration Register (Offset 0044h-0047h, R/W)

This register is used to set the receive configuration for the RTL8139D(L). Receive properties such as accepting error packets, runt packets, setting the receive drain threshold etc. are controlled here.

Bit	R/W	Symbol	Description
31-28	-	•	Reserved
27-24	R/W	ERTH3, 2, 1, 0	Early Rx threshold bits: These bits are used to select the Rx threshold multiplier of the whole packet that has been transferred to the system buffer in early mode when the frame protocol is under the RTL8139D(L)'s definition. $0000 = \text{no early rx threshold}$ $0001 = 1/16$ $0010 = 2/16$ $0011 = 3/16$ $0100 = 4/16$ $0101 = 5/16$ $0110 = 6/16$ $0111 = 7/16$ $1000 = 8/16$ $1001 = 9/16$ $1010 = 10/16$ $1011 = 11/16$ $1101 = 13/16$ $1101 = 13/16$



Bit	R/W	Symbol	Description
		•	1110 = 14/16
23-18	-	-	Reserved
17	R/W	MulERINT	Multiple early interrupt select: When this bit is set, any received
			packet invokes early interrupt according to MULINT <misr[11:0]></misr[11:0]>
			setting in early mode. When this bit is reset, the packets of familiar
			protocols (IPX, IP, NDIS, etc) invoke an early interrupt according to RCR <erth[3:0]> setting in early mode. The packets of unfamiliar</erth[3:0]>
			protocols will invoke an early interrupt according to the setting of
			MULINT <misr[11:0]>.</misr[11:0]>
16	R/W	RER8	The RTL8139D(L) receives the error packet whose length is larger than
			8 bytes after setting the RER8 bit to 1.
			The RTL8139D(L) receives the error packet larger than 64-byte long
			when the RER8 bit is cleared. The power-on default is zero.
			If AER or AR is set, the RER will be set when the RTL8139D(L)
			receives an error packet whose length is larger than 8 bytes. The RER8 is "Don't care" in this situation.
15-13	R/W	RXFTH2, 1, 0	Rx FIFO Threshold: Specifies Rx FIFO Threshold level. When the
13-13	IX/ VV	KAI 1112, 1, 0	number of the received data bytes from a packet, which is being received
			into the RTL8139D(L)'s Rx FIFO, has reached to this level (or the FIFO
			has contained a complete packet), the receive PCI bus master function
			will begin to transfer the data from the FIFO to the host memory. This
			field sets the threshold level according to the following table:
			000 = 16 bytes
			001 = 32 bytes
			010 = 64 bytes 011 = 128 bytes
			100 = 256 bytes
			101 = 512 bytes
			110 = 1024 bytes
			111 = no rx threshold. The RTL8139D(L) begins the transfer of data
			after having received a whole packet in the FIFO.
12-11	R/W	RBLEN1, 0	<b>Rx Buffer Length:</b> This field indicates the size of the Rx ring buffer.
			00 = 8k + 16 byte
			01 = 16k + 16 byte 10 = 32K + 16 byte
			10 - 32K + 16  byte 11 = 64K + 16  byte
10-8	R/W	MXDMA2, 1, 0	Max DMA Burst Size per Rx DMA Burst: This field sets the maximum
		,,	size of the receive DMA data bursts according to the following table:
			000 = 16 bytes
			001 = 32  bytes
			010 = 64 bytes
			011 = 128 bytes
			100 = 256 bytes 101 = 512 bytes
			110 = 1024 bytes
			111 = unlimited
7	R/W	WRAP	When set to 0: The RTL8139D(L) will transfer the rest of the packet
			data into the beginning of the Rx buffer if this packet has not been
			completely moved into the Rx buffer and the transfer has arrived at the
1			end of the Rx buffer.

16



Bit	R/W	Symbol	Description
		·	When set to 1: The RTL8139D(L) will keep moving the rest of the packet data into the memory immediately after the end of the Rx buffer, if this packet has not been completely moved into the Rx buffer and the transfer has arrived at the end of the Rx buffer. The software driver must reserve at least 1.5K bytes buffer to accept the remainder of the packet. We assume that the remainder of the packet is X bytes. The next packet will be moved into the memory from the X byte offset at the top of the Rx buffer.  This bit is invalid when Rx buffer is selected to 64K bytes.
6	-	-	Reserved
5	R/W	AER	Accept Error Packet: When set to 1, all packets with CRC error, alignment error, and/or collided fragments will be accepted. When set to 0, all packets with CRC error, alignment error, and/or collided fragments will be rejected.
4	R/W	AR	<b>Accept Runt:</b> This bit allows the receiver to accept packets that are smaller than 64 bytes. The packet must be at least 8 bytes long to be accepted as a runt. Set to 1 to accept runt packets.
3	R/W	AB	Accept Broadcast packets: Set to 1 to accept, 0 to reject.
2	R/W	AM	Accept Multicast packets: Set to 1 to accept, 0 to reject.
1	R/W	APM	Accept Physical Match packets: Set to 1 to accept, 0 to reject.
0	R/W	AAP	<b>Accept</b> All Packets: Set to 1 to accept all packets with a physical destination address, 0 to reject.

17



# **5.9. 9346CR: 93C46 Command Register** (Offset 0050h, R/W)

This register is used for issuing commands to the RTL8139D(L). These commands are issued by setting the corresponding bits for the function. A warm software reset along with individual reset and enable/disable for transmitter and receiver are provided as well.

D:4	D/W	Crymb al			Description
Bit	R/W	Symbol			Description The Description Th
7-6	R/W	EEM1-0	_	Mode:	These 2 bits select the RTL8139D(L) operating
			mode.		
			EEM1	EEM0	Operating Mode
			0	0	Normal (RTL8139D(L) network/host communication mode)
			0	1	Auto-load: Entering this mode will make the RTL8139D(L) load the contents of 93C46 like when the RSTB signal is asserted. This auto-load operation will take about 2 ms. After it is completed, the RTL8139D(L) goes back to the normal mode automatically (EEM1 = EEM0 = 0) and all the other registers are reset to default values.
			1	0	93C46 programming: In this mode, both network and host bus master operations are disabled. The 93C46 can be directly accessed via bit3-0 which now reflect the states of EECS, EESK, EEDI, & EEDO pins respectively.
			1	1	Config register write enable: Before writing to CONFIG0, 1, 3, 4 registers, and bit13, 12, 8 of BMCR(offset 62h-63h), the RTL8139D(L) must be placed in this mode. This will prevent RTL8139D(L)'s configurations from accidental change.
4-5	-	-	Reserved		
3	R/W	EECS	These bits i	reflect the	e state of EECS, EESK, EEDI & EEDO pins in
2	R/W	EESK	auto-load o	r 93C46 j	programming mode.
1	R/W	EEDI			
0	R	EEDO			



# 5.10. CONFIG 0: Configuration Register 0 (Offset 0051h, R/W)

Bit	R/W	Symbol		De	scription	
7	R	SCR	Scrambler Mode: Always 0.			
6	R	PCS	PCS Mode: Alv	vays 0.		
5	R	T10	10Mbps Mode:	Always 0.		
4-3	R	PL1, PL0	Select 10Mbps	medium type: A	Always (PL1,	PL0) = (1, 0)
2-0	R	BS2, BS1, BS0	Select Boot RO	<b>M size</b> (Autoloa	ded from EEI	PROM)
			BS2	BS1	BS0	Description
			0	0	0	No Boot ROM
			0	0	1	8K Boot ROM
			0	1	0	16K Boot ROM
			0	1	1	32K Boot ROM
			1	0	0	64K Boot ROM
			1	0	1	128K Boot ROM
			1	1	0	unused
			1	1	1	unused
				<u> </u>	<u> </u>	



## 5.11. CONFIG 1: Configuration Register 1

## (Offset 0052h, R/W)

Bit	R/W	Symbol			Description		
7-6	R/W	LEDS1-0	Refer to LED PIN defin	ition	. These bits initial value c	come from 93C46.	
5	R/W	DVRLOAD	<b>Driver Load:</b> Software may use this bit to make sure that the driver has been loaded. Writing 1 is 1. Writing 0 is 0. When the command register bits IOEN, MEMEN, and BMEN of the PCI configuration space are written, the			EN,	
4	R/W	LWACT	RTL8139D(L) will clear this bit automatically. <b>LWAKE active mode:</b> The LWACT bit and LWPTN bit in CONFIG4 register are used to program the LWAKE pin's output signal. According to the combination of these two bits, there may be 4 choices of LWAKE signal, i.e., active high, active low, positive (high) pulse, and negative (low) pulse. The output pulse width is about 150ms.  The default value of each of these two bits is 0, i.e., the default output signal of LWAKE pin is an active high signal.			the i.e., The	
			LWAKE outp	ut	LWA	CT	
					0	1	
			LWPTN	0	Active high*	Active low	
				1	Positive pulse	Negative pulse	]
_			* Default value.				
3	R	MEMMAP		_	rational registers are mapp		ace.
2	R	IOMAP			nal registers are mapped in		
1	R/W	VPD	Set to enable Vital Pro offset 40h-7Fh.	duct	<b>Data:</b> The VPD data is sto	ored in 93C46 from wi	thin
0	R/W	PMEn	Let A denote the New Configuration space off Let B denote the Cap_P Let C denote the Cap_II space offset 50H.  Let D denote the powe offset from 52H to 57H Let E denote the Next_F space offset 51H.  PMEn Description  0 A=B=C=E=0,	C46C w_Ca set 00 tr reg D (po r man tr (po	R register EEM1=EEM0=p bit (bit 4 of the State 6H. gister in the PCI Configurations wer management) register magement registers in the ower management) registers.	tus Register) in the ation space offset 34H r in the PCI Configura  PCI Configuration sp	I. tion pace



## 5.12. Media Status Register

## (Offset 0058h, R/W)

This register allows configuration of device and PHY options, and provides PHY status information.

Bit	R/W	Symbol	Description
7	R/W	TXFCE/ LdTXFCE	<b>Tx Flow Control Enable:</b> The flow control is valid in full-duplex mode only. This register's default value comes from 93C46.
			RTL8139D(L) Remote TXFCE/LdTXFCE
			ANE = 1 NWAY FLY mode R/O
			ANE = 1 NWAY mode only R/W
			ANE = 1 No NWAY R/W
			ANE = 0 & R/W
			full-duplex mode
			ANE = 0 & invalid
			half-duplex mode
			NWAY FLY mode: NWAY with flow control capability NWAY mode only: NWAY without flow control capability
6	R/W	RXFCE	<b>RX Flow control Enable:</b> The flow control is enabled in full-duplex
			mode only. The default value comes from 93C46.
5	-	-	Reserved
4	R	Aux_Status	Aux. Power present Status:
			1: The Aux. Power is present.
			0: The Aux. Power is absent.
3	D	CDEED 10	The value of this bit is fixed after each PCI reset.
3	R	SPEED_10	<b>Speed:</b> Set, when current media is 10 Mbps mode. Reset, when current media is 100 Mbps mode.
2	R	LINKB	Inverse of Link status. 0 = Link OK. 1 = Link Fail.
1	R	TXPF	Transmit Pause Flag: Set, when RTL8139D(L) sends pause packet.
			Reset, when RTL8139D(L) sends a timer done packet.
0	R	RXPF	Receive Pause Flag: Set, when RTL8139D(L) is in backoff state
			because a pause packet was received. Reset, when pause state is clear.



## 5.13. CONFIG 3: Configuration Register3

## (Offset 0059h, R/W)

Bit	R/W	Symbol	Description
7	R	GNTSel	Gnt Select: Select the Frame's asserted time after the Grant signal has been asserted. The Frame and Grant are the PCI signals.  0: No delay 1: delay one clock from GNT assertion.
6	R/W	PARM_En	Parameter Enable: (Used in 100Mbps mode only) This set to 0 and the 9346CR register EEM1=EEM0=1 will enable the PHY1_PARM, PHY2_PARM, and TW_PARM registers to be written via software. This set to 1 will allow parameters to be auto-loaded from the 93C46 and disable writing to the PHY1_PARM, PHY2_PARM and TW_PARM registers via software. The PHY1_PARM and PHY2_PARM can be auto-loaded from the EEPROM in this mode. The parameter auto-load process is executed every time the Link is OK in 100Mbps mode.
5	R/W	Magic	Magic Packet: This bit is valid when the PWEn bit of the CONFIG1 register is set. The RTL8139D(L) will assert the PMEB signal to wakeup the operating system when the Magic Packet is received.  Once the RTL8139D(L) has been enabled for Magic Packet wakeup and has been put into adequate state, it scans all incoming packets addressed to the node for a specific data sequence, which indicates to the controller that this is a Magic Packet frame. A Magic Packet frame must also meet the basic requirements of:  Destination address + Source address + data + CRC  The destination address may be the node ID of the receiving station or a multicast address, which includes the broadcast address.  The specific sequence consists of 16 duplications of 6 byte ID registers, with no breaks or interrupts. This sequence can be located anywhere within the packet, but must be preceded by a synchronization stream, 6 bytes of FFh. The device will also accept a multicast address, as long as the 16 duplications of the IEEE address match the address of the ID registers. If the Node ID is 11h 22h 33h 44h 55h 66h, then the magic frame's format is similar to the following:  Destination address + source address + MISC + FF FF FF FF FF FF FF HMISC + 11 22 33 44 55 66 + 11 22 33 44
4	R/W	LinkUp	<b>Link Up:</b> This bit is valid when the PWEn bit of CONFIG1 register is set. The RTL8139D(L), in adequate power state, will assert the PMEB signal to
			wakeup the operating system when the cable connection is re-established.
3	- D	CLUDIDI E	Reserved
2	R	CLKRUN_En	CLKRUN Enable: Set to 0 to disable CLKRUN Set to 1 to enable CLKRUN
1	-	=	Reserved
0	R	FBtBEn	Fast Back to Back Enable: Set to 1 to enable Fast Back to Back.



# 5.14. CONFIG 4: Configuration Register4 (Offset 005Ah, R/W)

Bit	R/W	Symbol	Description
7	R/W	RxFIFOAutoClr	Set to 1, the RTL8139D(L) will clear the Rx FIFO overflow automatically.
6	R/W	AnaOff	Analog Power Off: This bit can not be auto-loaded from EEPROM (93C46).  1: Turn off the analog power of the RTL8139D(L) internally.  0: Normal working state. This is also power-on default value.
5	R/W	LongWF	Long Wake-up Frame: The initial value comes from EEPROM autoload.  Set to 1: The RTL8139D(L) supports up to 5 wake-up frames, each with 16-bit CRC algorithm for MS Wakeup Frame, the low byte of 16-bit CRC should be placed at the correspondent CRC register, and the high byte of 16-bit CRC should be placed at the correspondent LSBCRC register. The wake-up frame 0 and 1 are the same as above, except that the masked bytes start from offset 0 to 63. The wake-up frame 2 and 3 are merged into one long wake-up frame respectively with masked bytes selected from offset 0 to 127. The wake-up frame 4 and 5, 6 and 7 are merged respectively into another 2 long wake-up frames. Refer to 7.4 PCI Power Management Functions, page 41 for a detailed description.  Set to 0: The RTL8139D(L) supports up to 8 wake-up frames, each with masked bytes selected from offset 12 to 75.
4	R/W	LWPME	LANWAKE vs PMEB: Set to 1: The LWAKE can only be asserted when the PMEB is asserted and the ISOLATEB is low. Set to 0: The LWAKE and PMEB are asserted at the same time.
3	-	-	Reserved
2	R/W	LWPTN	<b>LWAKE pattern:</b> Please refer to LWACT bit in CONFIG1 register.
1	-	-	Reserved
0	R/W	PBWakeup	Pre-Boot Wakeup: The initial value comes from EEPROM autoload.  1: Pre-Boot Wakeup disabled. (suitable for CardBus and MiniPCI applications)  0: Pre-Boot Wakeup enabled.



## 5.15. Multiple Interrupt Select Register (Offset 005Ch-005Dh, R/W)

If the received packet data is not a familiar protocol (IPX, IP, NDIS, etc.) to the RTL8139D(L), RCR<ERTH[3:0]> won't be used to transfer data in early mode. This register will be written to the received data length in order to make an early Rx interrupt for the unfamiliar protocol.

Bit	R/W	Symbol	Description
15-12	-	-	Reserved
11-0	R/W	MISR11-0	Multiple Interrupt Select: Indicates that the RTL8139D(L) makes an rx interrupt after RTL8139D(L) has transferred the byte data into the system memory. If the value of these bits is zero, there will be no early interrupt as soon as the RTL8139D(L) prepares to execute the first PCI transaction of the received data. Bit1, 0 must be zero. The ERTH3-0 bits should not be set to 0 when the multiple interrupt select register is used.

Note: The above is true when MulERINT=0 (bit17, RCR). When MulERINT=1, any received packet invokes early interrupt according to the MISR[11:0] setting in early mode.

#### 5.16. PCI Revision ID

#### (Offset 005Eh, R)

Bit	R/W	Symbol	Description
7-0	R	Revision ID	The value in PCI Configuration Space offset 08h is 10h.

## 5.17. Transmit Status of All Descriptors (TSAD) Register (Offset 0060h-0061h, R/W)

Bit	R/W	Symbol	Description
15	R	TOK3	TOK bit of Descriptor 3
14	R	TOK2	TOK bit of Descriptor 2
13	R	TOK1	TOK bit of Descriptor 1
12	R	TOK0	TOK bit of Descriptor 0
11	R	TUN3	TUN bit of Descriptor 3
10	R	TUN2	TUN bit of Descriptor 2
9	R	TUN1	TUN bit of Descriptor 1
8	R	TUN0	TUN bit of Descriptor 0
7	R	TABT3	TABT bit of Descriptor 3
6	R	TABT2	TABT bit of Descriptor 2
5	R	TABT1	TABT bit of Descriptor 1
4	R	TABT0	TABT bit of Descriptor 0
3	R	OWN3	OWN bit of Descriptor 3
2	R	OWN2	OWN bit of Descriptor 2
1	R	OWN1	OWN bit of Descriptor 1
0	R	OWN0	OWN bit of Descriptor 0



## 5.18. Basic Mode Control Register

## (Offset 0062h-0063h, R/W)

Bit	Name	Description/Usage	<b>Default/Attribute</b>
15	Reset	This bit sets the status and control registers of the PHY(register	0, RW
		0062-0074H) in a default state. This bit is self-clearing. 1 = software	
		reset; $0 = \text{normal operation}$ .	
14	-	Reserved	-
13	Spd_Set	This bit sets the network speed. $1 = 100$ Mbps; $0 = 10$ Mbps. This bit's	0, RW
		initial value comes from 93C46.	
12	Auto Negotiation	This bit enables/disables the NWay auto-negotiation function.	0, RW
	Enable	Set to 1 to enable auto-negotiation, bit13 will be ignored.	
	(ANE)	Set to 0 disables auto-negotiation, bit13 and bit8 will determine the	
		link speed and the data transfer mode, respectively.	
		This bit's initial value comes from 93C46.	
11-10	-	Reserved	-
9	Restart Auto	This bit allows the NWay auto-negotiation function to be reset.	0, RW
	Negotiation	1 = re-start auto-negotiation; 0 = normal operation.	
8	<b>Duplex Mode</b>	This bit sets the duplex mode. $0 = \text{normal operation}$ ; $1 = \text{full-duplex}$ .	0, RW
		This bit's initial value comes from 93C46.	
		If bit12 = 1, read = status write = register value.	
		If $bit12 = 0$ , read = write = register value.	
7-0	-	Reserved	=

25



### 5.19. Basic Mode Status Register

### (Offset 0064h-0065h, R)

Bit	Name	Description/Usage	Default/Attribute
15	100Base-T4	1 = enable 100Base-T4 support; 0 = suppress 100Base-T4 support.	0, RO
14	100Base_TX_FD	1 = enable 100Base-TX full duplex support;	1, RO
		0 = suppress 100Base-TX full duplex support.	
13	100BASE_TX_HD	1 = enable 100Base-TX half-duplex support;	1, RO
		0 = suppress 100Base-TX half-duplex support.	
12	10Base_T_FD	1 = enable 10Base-T full duplex support;	1, RO
		0 = suppress 10Base-T full duplex support.	
11	10_Base_T_HD	1 = enable 10Base-T half-duplex support;	1, RO
		0 = suppress 10Base-T half-duplex support.	
10-6	-	Reserved	-
5	Auto Negotiation	1 = auto-negotiation process completed;	0, RO
	Complete	0 = auto-negotiation process not completed.	
4	Remote Fault	1 = remote fault condition detected (cleared on read);	0, RO
		0 = no remote fault condition detected.	
3	Auto Negotiation	1 = Link had not been experienced fail state.	1, RD
		0 = Link had been experienced fail state	
2	Link Status	1 = valid link established;	0, RO
		0 = no valid link established.	
1	Jabber Detect	1 = jabber condition detected; 0 = no jabber condition detected.	0, RO
0	Extended	1 = extended register capability;	1, RO
	Capability	0 = basic register capability only.	

# 5.20. Auto-negotiation Advertisement Register (Offset 0066h-0067h, R/W)

This register contains the advertised abilities of this device as they will be transmitted to its link partner during Auto-negotiation.

Bit	Name	Description/Usage	Default/Attribute
15	NP	Next Page bit.	0, RO
		1 = transmitting the protocol specific data page;	
		0 = transmitting the primary capability data page	
14	ACK	1 = acknowledge reception of link partner capability data word.	0, RO
13	RF	1 = advertise remote fault detection capability;	0, RW
		0 = do not advertise remote fault detection capability.	
12-11	-	Reserved	-
10	Pause	1 = flow control is supported by local node.	The default value
		0 = flow control is not supported by local mode.	comes from
			EEPROM, RO
9	T4	1 = 100Base-T4 is supported by local node;	0, RO
		0 = 100Base-T4 not supported by local node.	
8	TXFD	1 = 100Base-TX full duplex is supported by local node;	1, RW
		0 = 100Base-TX full duplex not supported by local node.	



Bit	Name	Description/Usage	Default/Attribute
7	TX	1 = 100Base-TX is supported by local node;	1, RW
		0 = 100Base-TX not supported by local node.	
6	10FD	1 = 10Base-T full duplex supported by local node;	1, RW
		0 = 10Base-T full duplex not supported by local node.	
5	10	1 = 10Base-T is supported by local node;	1, RW
		0 = 10Base-T not supported by local node.	
4-0	Selector	Binary encoded selector supported by this node. Currently only	<00001>, RW
		CSMA/CD <00001> is specified. No other protocols are supported.	·

## 5.21. Auto-Negotiation Link Partner Ability Register (Offset 0068h-0069h, R)

This register contains the advertised abilities of the Link Partner as received during Auto-negotiation. The content changes after the successful Auto-negotiation if Next-pages are supported.

Bit	Name	Description/Usage	Default/Attribute
15	NP	Next Page bit.	0, RO
		1 = transmitting the protocol specific data page;	
		0 = transmitting the primary capability data page.	
14	ACK	1 = link partner acknowledges reception of local node's capability	0, RO
		data word.	
13	RF	1 = link partner is indicating a remote fault.	0, RO
12-11	-	Reserved	-
10	Pause	1 = Flow control is supported by link partner,	0, RO
		0 = Flow control is not supported by link partner.	
9	T4	1 = 100Base-T4 is supported by link partner;	0, RO
		0 = 100Base-T4 not supported by link partner.	
8	TXFD	1 = 100Base-TX full duplex is supported by link partner;	0, RO
		0 = 100Base-TX full duplex not supported by link partner.	
7	TX	1 = 100Base-TX is supported by link partner;	0, RO
		0 = 100Base-TX not supported by link partner.	
6	10FD	1 = 10Base-T full duplex is supported by link partner;	0, RO
		0 = 10Base-T full duplex not supported by link partner.	
5	10	1 = 10Base-T is supported by link partner;	0, RO
		0 = 10Base-T not supported by link partner.	
4-0	Selector	Link Partner's binary encoded node selector. Currently only	<00000>, RO
		CSMA/ CD <00001> is specified.	



## 5.22. Auto-negotiation Expansion Register (Offset 006Ah-006Bh, R)

This register contains additional status for NWay auto-negotiation.

Bit	Name	Description/Usage	Default/Attribute
15-5	-	Reserved, This bit is always set to 0.	-
4	MLF	Status indicating if a multiple link fault has occurred.	0, RO
		1 = fault occurred; 0 = no fault occurred.	
3	LP_NP_ABLE	Status indicating if the link partner supports Next Page negotiation.	0, RO
		1 = supported; $0 = $ not supported.	
2	NP_ABLE	This bit indicates if the local node is able to send additional Next	0, RO
		Pages.	
1	PAGE_RX	This bit is set when a new Link Code Word Page has been received.	0, RO
		The bit is automatically cleared when the auto-negotiation link	
		partner's ability register (register 5) is read by management.	
0	LP_NW_ABLE	1 = link partner supports NWay auto-negotiation.	0, RO

#### 5.23. Disconnect Counter

#### (Offset 006Ch-006Dh, R)

Bit	Name	Description/Usage	Default/Attribute
15-0	DCNT	This 16-bit counter increments by 1 for every disconnect event. It	h'[0000],
		rolls over when becomes full. It is cleared to zero by read	R
		command.	

## 5.24. False Carrier Sense Counter (Offset 006Eh-006Fh, R)

This counter provides information required to implement the "FalseCarriers" attribute within the MAU managed object class of Clause 30 of IEEE 802.3u specification.

Bit	Name	Description/Usage	Default/Attribute
15-0	FCSCNT	This 16-bit counter increments by 1 for each false carrier event. It is	h'[0000],
		cleared to zero by read command.	R



## 5.25. NWay Test Register (Offset 0070h-0071h, R/W)

Bit	Name	Description/Usage	Default/Attribute
15-8	-	Reserved	-
7	NWLPBK	1 = set NWay to loopback mode.	0, RW
6-4	-	Reserved	-
3	ENNWLE	1 = LED0 Pin indicates linkpulse	0, RW
2	FLAGABD	1 = Auto-neg experienced ability detect state	0, RO
1	FLAGPDF	1 = Auto-neg experienced parallel detection fault state	0, RO
0	FLAGLSC	1 = Auto-neg experienced link status check state	0, RO

## 5.26. RX\_ER Counter (Offset 0072h-0073h, R)

Bit	Name	Description/Usage	Default/Attribute
15-0	RXERCNT	This 16-bit counter increments by 1 for each valid packet received.	h'[0000],
		It is cleared to zero by a read command.	R

## 5.27. CS Configuration Register (Offset 0074h-0075h, R/W)

Bit	Name	Description/Usage	Default/Attribute
15	Testfun	1 = Auto-neg speeds up internal timer	0,WO
14-10	-	Reserved	-
9	LD	Active low TPI link disable signal. When low, TPI still transmits	1, RW
		link pulses and TPI stays in good link state.	
8	HEART BEAT	1 = HEART BEAT enable, 0 = HEART BEAT disable. HEART	1, RW
		BEAT function is only valid in 10Mbps mode.	
7	JBEN	1 = enable jabber function; $0 = $ disable jabber function	1, RW
6	F_LINK_100	Used to login force good link in 100Mbps for diagnostic purposes.	1, RW
		1 = DISABLE, 0 = ENABLE.	
5	F_Connect	Assertion of this bit forces the disconnect function to be bypassed.	0, RW
4	-	Reserved	-
3	Con_status	This bit indicates the status of the connection. 1 = valid connected	0, RO
		link detected; 0 = disconnected link detected.	
2	Con_status_En	Assertion of this bit configures LED1 pin to indicate connection	0, RW
		status.	
1	-	Reserved	-
0	PASS_SCR	Bypass Scramble	0, RW



# 5.28. Config5: Configuration Register 5 (Offset 00D8h, R/W)

This register, unlike other Config registers, is not protected by 93C46 Command register. I.e. there is no need to enable Config register write prior to writing to Config5.

Bit	R/W	Symbol	Description
7	-	<u>-</u>	Reserved
6	R/W	BWF	Broadcast Wakeup Frame:  1: Enable Broadcast Wakeup Frame with mask bytes of only DID field = FF FF FF FF FF.  0: Default value. Disable Broadcast Wakeup Frame with mask bytes of only DID field = FF FF FF FF FF.
			The power-on default value of this bit is 0.
5	R/W	MWF	<ul> <li>Multicast Wakeup Frame:</li> <li>1: Enable Multicast Wakeup Frame with mask bytes of only DID field, which is a multicast address.</li> <li>0: Default value. Disable Multicast Wakeup Frame with mask bytes of only DID field, which is a multicast address.</li> <li>The power-on default value of this bit is 0.</li> </ul>
4	R/W	UWF	Unicast Wakeup Frame:
			<ol> <li>Enable Unicast Wakeup Frame with mask bytes of only DID field, which is its own physical address.</li> <li>Default value. Disable Unicast Wakeup Frame with mask bytes of only DID field, which is its own physical address.</li> <li>The power-on default value of this bit is 0.</li> </ol>
3	R/W	FIFOAddrPtr	FIFO Address Pointer: (Realtek internal use only to test FIFO SRAM)  1: Both Rx and Tx FIFO address pointers are updated in descending way from 1FFh and downwards. The initial FIFO address pointer is 1FFh.  0: (Power-on) default value. Both Rx and Tx FIFO address pointers are updated in ascending way from 0 and upwards. The initial FIFO address pointer is 0.  Note: This bit does not participate in EEPROM auto-load. The FIFO address pointers can not be reset, except initial power-on.  The power-on default value of this bit is 0.
2	R/W	LDPS	Link Down Power Saving mode:  1: Disable.  0: Enable. When cable is disconnected (Link Down), the analog part will power down itself (PHY Tx part & part of twister) automatically except PHY Rx part and part of twister to monitor SD signal in case that cable is re-connected and Link should be established again.
1	R/W	LANWake	LANWake signal enable/disable:  1: Enable LANWake signal.  0: Disable LANWake signal.
0	R/W	PME_STS	PME_Status bit: Always sticky/can be reset by PCI RST# and software.  1: The PME_Status bit can be reset by PCI reset or by software.  0: The PME_Status bit can only be reset by software.

Config5 register, offset D8h: (SYM\_ERR register is changed to Config5, the function of SYM\_ERR register is no longer supported by RTL8139D(L).)

<sup>➤</sup> The 3 bits (bit2-0) are auto-loaded from EEPROM Config5 byte to RTL8139D(L) Config5 register.



# 6. EEPROM (93C46) Contents

The 93C46 is a 1K-bit EEPROM. Although it is addressed by words, we list its contents by bytes below for convenience.

The 93C46 is a 1K-bit EEPROM. Although it is actually addressed by words, its contents are listed below by bytes for convenience. After the valid duration of the RSTB pin or auto-load command in the 9346CR, the RTL8139D(L) performs a series of EEPROM read operations from the 93C46 addresses 00H to 31H.

It is suggested to obtain Realtek approval before changing the default settings of the EEPROM.

Olh			
Olh	Bytes	Contents	
Olh	00h	29h	These 2 bytes contain the ID code word for the RTL8139D(L). The RTL8139D(L) will
Dock-05h   Converse   Process   Pr	01h	81h	load the contents of EEPROM into the corresponding location if the ID word (8129h) is
O2h-O5h			right, otherwise, the RTL8139D(L) will not proceed with the EEPROM autoload
The default values of VID and DID are hex 10EC and 8139, respectively.    O6h-07h			process.
O6h-07h	02h-05h	-	Reserved. The RTL8139D(L) no longer supports autoload of Vender ID and Device ID.
O8h-09h   SMID   PCI Subsystem ID, PCI configuration space offset 2Eh-2Fh.			The default values of VID and DID are hex 10EC and 8139, respectively.
OAh	06h-07h	SVID	PCI Subsystem Vendor ID, PCI configuration space offset 2Ch-2Dh.
OBh   MXLAT   PCI Maximum Latency Timer, PCI configuration space offset 3Fh.	08h-09h	SMID	PCI Subsystem ID, PCI configuration space offset 2Eh-2Fh.
OBh   MXLAT   PCI Maximum Latency Timer, PCI configuration space offset 3Fh.	0Ah	MNGNT	PCI Minimum Grant Timer, PCI configuration space offset 3Eh.
OCh MSRBMCR Bits 7-6 map to bits 7-6 of the Media Status register (MSR); Bits 5, 4, 0 map to bits 13, 12, 8 of the Basic Mode Control register (BMCR); Bits 3-2 are reserved. If the network speed is set to Auto-Detect mode (i.e. Nway mode), then Bit 1=0 means the local RTL8139D(L) supports flow control (IEEE 802.3x). In this case, Bit 10=1 in the Auto-negotiation Advertisement Register (offset 66h-67h), and Bit 1=1 means the local RTL8139D(L) does not support flow control. In this case, Bit 10=0 in Auto-negotiation Advertisement. This is because there are Nway switch hubs which keep sending flow control pause packets for no reason, if the link partner supports Nway flow control.  ODh CONFIG3 RTL8139D(L) Configuration register 3, operational register offset 59H.  Ethernet ID Ethernet ID, After auto-load command or hardware reset, RTL8139D(L) loads Ethernet ID to IDR0-IDR5 of RTL8139D(L)'s I/O registers.  14h CONFIG0 RTL8139D(L) Configuration register 0, operational registers offset 51h.  15h CONFIG1 RTL8139D(L) Configuration register 1, operational registers offset 52h.  16h-17h PMC Reserved. Do not change this filed without Realtek approval. Power Management Capabilities. PCI configuration space address 52h and 53h.  Reserved. Do not change this filed without Realtek approval. Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval. RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval. Pry Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are	0Bh	MXLAT	
12, 8 of the Basic Mode Control register (BMCR); Bits 3-2 are reserved. If the network speed is set to Auto-Detect mode (i.e. Nway mode), then Bit 1=0 means the local RTL8139D(L) supports flow control (IEEE 802.3x). In this case, Bit 10=1 in the Auto-negotiation Advertisement Register (offset 66h-67h), and Bit 1=1 means the local RTL8139D(L) does not support flow control. In this case, Bit 10=0 in Auto-negotiation Advertisement. This is because there are Nway switch hubs which keep sending flow control pause packets for no reason, if the link partner supports Nway flow control.  ODh CONFIG3 RTL8139D(L) Configuration register 3, operational register offset 59H.  Ethernet ID Ethernet ID, After auto-load command or hardware reset, RTL8139D(L) loads Ethernet ID to IDR0-IDR5 of RTL8139D(L)'s I/O registers.  14h CONFIG0 RTL8139D(L) Configuration register 0, operational registers offset 51h.  15h CONFIG1 RTL8139D(L) Configuration register 1, operational registers offset 52h.  16h-17h PMC Reserved. Do not change this filed without Realtek approval.  Power Management Capabilities. PCI configuration space address 52h and 53h.  Reserved. Do not change this filed without Realtek approval.  Power Management Control/Status. PCI configuration space address 55h.  Reserved. Do not change this filed without Realtek approval.  RESERVED. Do not change this filed without Realtek approval.  RESERVED. On the Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval.  PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are			
speed is set to Auto-Detect mode (i.e. Nway mode), then Bit 1=0 means the local RTL8139D(L) supports flow control (IEEE 802.3x). In this case, Bit 10=1 in the Auto-negotiation Advertisement Register (offset 66h-67h), and Bit 1=1 means the local RTL8139D(L) does not support flow control. In this case, Bit 10=0 in Auto-negotiation Advertisement. This is because there are Nway switch hubs which keep sending flow control pause packets for no reason, if the link partner supports Nway flow control.  ODh CONFIG3 RTL8139D(L) Configuration register 3, operational register offset 59H.  Ethernet ID Ethernet ID, After auto-load command or hardware reset, RTL8139D(L) loads Ethernet ID to IDR0-IDR5 of RTL8139D(L)'s I/O registers.  14h CONFIG0 RTL8139D(L) Configuration register 0, operational registers offset 51h.  15h CONFIG1 RTL8139D(L) Configuration register 1, operational registers offset 52h.  16h-17h PMC Reserved. Do not change this filed without Realtek approval.  Power Management Capabilities. PCI configuration space address 52h and 53h.  18h PMCSR Reserved. Do not change this filed without Realtek approval.  Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval.  RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval.  PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are			
RTL8139D(L) supports flow control (IEEE 802.3x). In this case, Bit 10=1 in the Auto-negotiation Advertisement Register (offset 66h-67h), and Bit 1=1 means the local RTL8139D(L) does not support flow control. In this case, Bit 10=0 in Auto-negotiation Advertisement. This is because there are Nway switch hubs which keep sending flow control pause packets for no reason, if the link partner supports Nway flow control.  ODh CONFIG3 RTL8139D(L) Configuration register 3, operational register offset 59H.  Ethernet ID Ethernet ID, After auto-load command or hardware reset, RTL8139D(L) loads Ethernet ID to IDR0-IDR5 of RTL8139D(L)'s I/O registers.  14h CONFIG0 RTL8139D(L) Configuration register 0, operational registers offset 51h.  15h CONFIG1 RTL8139D(L) Configuration register 1, operational registers offset 52h.  Reserved. Do not change this filed without Realtek approval.  Power Management Capabilities. PCI configuration space address 52h and 53h.  Reserved. Do not change this filed without Realtek approval.  Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval.  RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval.  PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are			
Auto-negotiation Advertisement Register (offset 66h-67h), and Bit 1=1 means the local RTL8139D(L) does not support flow control. In this case, Bit 10=0 in Auto-negotiation Advertisement. This is because there are Nway switch hubs which keep sending flow control pause packets for no reason, if the link partner supports Nway flow control.  ODh CONFIG3 RTL8139D(L) Configuration register 3, operational register offset 59H.  Ethernet ID Ethernet ID, After auto-load command or hardware reset, RTL8139D(L) loads Ethernet ID to IDR0-IDR5 of RTL8139D(L)'s I/O registers.  14h CONFIG0 RTL8139D(L) Configuration register 0, operational registers offset 51h.  15h CONFIG1 RTL8139D(L) Configuration register 1, operational registers offset 52h.  PMC Reserved. Do not change this filed without Realtek approval.  Power Management Capabilities. PCI configuration space address 52h and 53h.  Reserved. Do not change this filed without Realtek approval.  Power Management Control/Status. PCI configuration space address 55h.  Reserved. Do not change this filed without Realtek approval.  RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval.  PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are			
RTL8139D(L) does not support flow control. In this case, Bit 10=0 in Auto-negotiation Advertisement. This is because there are Nway switch hubs which keep sending flow control pause packets for no reason, if the link partner supports Nway flow control.  ODh CONFIG3 RTL8139D(L) Configuration register 3, operational register 59H.  Ethernet ID Ethernet ID, After auto-load command or hardware reset, RTL8139D(L) loads Ethernet ID to IDR0-IDR5 of RTL8139D(L)'s I/O registers.  14h CONFIG0 RTL8139D(L) Configuration register 0, operational registers offset 51h.  15h CONFIG1 RTL8139D(L) Configuration register 1, operational registers offset 52h.  16h-17h PMC Reserved. Do not change this filed without Realtek approval.  Power Management Capabilities. PCI configuration space address 52h and 53h.  18h PMCSR Reserved. Do not change this filed without Realtek approval.  Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval.  RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval.  PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are			Auto-negotiation Advertisement Register (offset 66h-67h), and Bit 1=1 means the local
control pause packets for no reason, if the link partner supports Nway flow control.  ODh CONFIG3 RTL8139D(L) Configuration register 3, operational register offset 59H.  Ethernet ID Ethernet ID, After auto-load command or hardware reset, RTL8139D(L) loads Ethernet ID to IDR0-IDR5 of RTL8139D(L)'s I/O registers.  14h CONFIG0 RTL8139D(L) Configuration register 0, operational registers offset 51h.  15h CONFIG1 RTL8139D(L) Configuration register 1, operational registers offset 52h.  16h-17h PMC Reserved. Do not change this filed without Realtek approval.  Power Management Capabilities. PCI configuration space address 52h and 53h.  18h PMCSR Reserved. Do not change this filed without Realtek approval.  Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval.  RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval.  PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are			RTL8139D(L) does not support flow control. In this case, Bit 10=0 in Auto-negotiation
ODh CONFIG3 RTL8139D(L) Configuration register 3, operational register offset 59H.  OEh-13h Ethernet ID Ethernet ID, After auto-load command or hardware reset, RTL8139D(L) loads Ethernet ID to IDR0-IDR5 of RTL8139D(L)'s I/O registers.  14h CONFIG0 RTL8139D(L) Configuration register 0, operational registers offset 51h.  15h CONFIG1 RTL8139D(L) Configuration register 1, operational registers offset 52h.  16h-17h PMC Reserved. Do not change this filed without Realtek approval. Power Management Capabilities. PCI configuration space address 52h and 53h.  18h PMCSR Reserved. Do not change this filed without Realtek approval. Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval. RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval. PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are			Advertisement. This is because there are Nway switch hubs which keep sending flow
DEh-13h			control pause packets for no reason, if the link partner supports Nway flow control.
ID to IDR0-IDR5 of RTL8139D(L)'s I/O registers.  14h CONFIG0 RTL8139D(L) Configuration register 0, operational registers offset 51h.  15h CONFIG1 RTL8139D(L) Configuration register 1, operational registers offset 52h.  16h-17h PMC Reserved. Do not change this filed without Realtek approval. Power Management Capabilities. PCI configuration space address 52h and 53h.  18h PMCSR Reserved. Do not change this filed without Realtek approval. Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval. RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval. PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are	0Dh	CONFIG3	RTL8139D(L) Configuration register 3, operational register offset 59H.
14hCONFIG0RTL8139D(L) Configuration register 0, operational registers offset 51h.15hCONFIG1RTL8139D(L) Configuration register 1, operational registers offset 52h.16h-17hPMCReserved. Do not change this filed without Realtek approval. Power Management Capabilities. PCI configuration space address 52h and 53h.18hPMCSRReserved. Do not change this filed without Realtek approval. Power Management Control/Status. PCI configuration space address 55h.19hCONFIG4Reserved. Do not change this filed without Realtek approval. RTL8139D(L) Configuration register 4, operational registers offset 5Ah.1Ah-1DhPHY1_PARM_UReserved. Do not change this filed without Realtek approval. PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are	0Eh-13h	Ethernet ID	Ethernet ID, After auto-load command or hardware reset, RTL8139D(L) loads Ethernet
15h CONFIG1 RTL8139D(L) Configuration register 1, operational registers offset 52h.  16h-17h PMC Reserved. Do not change this filed without Realtek approval. Power Management Capabilities. PCI configuration space address 52h and 53h.  18h PMCSR Reserved. Do not change this filed without Realtek approval. Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval. RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval. PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are			ID to IDR0-IDR5 of RTL8139D(L)'s I/O registers.
16h-17h PMC Reserved. Do not change this filed without Realtek approval. Power Management Capabilities. PCI configuration space address 52h and 53h.  18h PMCSR Reserved. Do not change this filed without Realtek approval. Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval. RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval. PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are	14h	CONFIG0	RTL8139D(L) Configuration register 0, operational registers offset 51h.
Power Management Capabilities. PCI configuration space address 52h and 53h.  18h PMCSR Reserved. Do not change this filed without Realtek approval. Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval. RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval. PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are	15h	CONFIG1	RTL8139D(L) Configuration register 1, operational registers offset 52h.
18h PMCSR Reserved. Do not change this filed without Realtek approval. Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval. RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval. PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are	16h-17h	PMC	Reserved. Do not change this filed without Realtek approval.
Power Management Control/Status. PCI configuration space address 55h.  19h CONFIG4 Reserved. Do not change this filed without Realtek approval.  RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval.  PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are			Power Management Capabilities. PCI configuration space address 52h and 53h.
19h CONFIG4 Reserved. Do not change this filed without Realtek approval. RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval. PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are	18h	PMCSR	Reserved. Do not change this filed without Realtek approval.
RTL8139D(L) Configuration register 4, operational registers offset 5Ah.  1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval. PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are			Power Management Control/Status. PCI configuration space address 55h.
1Ah-1Dh PHY1_PARM_U Reserved. Do not change this filed without Realtek approval. PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are	19h	CONFIG4	Reserved. Do not change this filed without Realtek approval.
PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are			RTL8139D(L) Configuration register 4, operational registers offset 5Ah.
	1Ah-1Dh	PHY1_PARM_U	Reserved. Do not change this filed without Realtek approval.
from 78h to 7Bh.			PHY Parameter 1-U for RTL8139D(L). Operational registers of the RTL8139D(L) are
			from 78h to 7Bh.
1Eh PHY2_PARM_U Reserved. Do not change this filed without Realtek approval.	1Eh	PHY2_PARM_U	Reserved. Do not change this filed without Realtek approval.
PHY Parameter 2-U for RTL8139D(L). Operational register of the RTL8139D(L) is			PHY Parameter 2-U for RTL8139D(L). Operational register of the RTL8139D(L) is
80h.			80h.
1Fh CONFIG 5 Do not change this filed without Realtek approval.	1Fh	CONFIG 5	Do not change this filed without Realtek approval.



Bytes	Contents	Description
		Bit7-6,4-3: Reserved.
		Bit5: PCI multi-function enable.
		Set to 1: Enable PCI multi-function capability. The RTL8139D(L) can be a multi-function device with an external master PCI device mode on the same PCB, ex. an external hardware modem.  Set to 0: Disable PCI multi-function capability.
		Bit2: Link Down Power Saving mode:
		Set to 1: Disable.
		Set to 0: Enable. When cable is disconnected(Link Down), the analog part will power down itself (PHY Tx part & part of twister) automatically except PHY Rx part and part of twister to monitor SD signal in case that cable is re-connected and Link should be established again.  Bit1: LANWake signal Enable/Disable
		Set to 1: Enable LANWake signal.
		Set to 0: Disable LANWake signal.
		Bit0: PME Status bit property
		Set to 1: The PME_Status bit can be reset by PCI reset or by software if D3cold_support_PME is 0. If D3cold_support_PME=1, the PME_Status bit is a sticky bit.  Set to 0: The PME Status bit is always a sticky bit and can only be reset by software.
20h-23h	TW PARM U	Reserved. Do not change this filed without Realtek approval.
2011 2011	11,111111111111111111111111111111111111	Twister Parameter U for RTL8139D(L). Operational registers of the RTL8139D(L) are 7Ch-7Fh.
24h-27h	TW_PARM_T	Reserved. Do not change this filed without Realtek approval. Twister Parameter T for RTL8139D(L). Operational registers of the RTL8139D(L) are 7Ch-7Fh.
28h-2Bh	PHY1_PARM_T	Reserved. Do not change this filed without Realtek approval. PHY Parameter 1-T for RTL8139D(L). Operational registers of the RTL8139D(L) are from 78h to 7Bh.
2Ch	PHY2_PARM_T	Reserved. Do not change this filed without Realtek approval. PHY Parameter 2-T for RTL8139D(L). Operational register of the RTL8139D(L) is 80h.
2Dh-31h	-	Reserved.
32h-33h	CheckSum	Reserved. Do not change this filed without Realtek approval. Checksum of the EEPROM content.
34h-3Eh	-	Reserved. Do not change this filed without Realtek approval.
3Fh	PXE_Para	Reserved. Do not change this filed without Realtek approval. PXE ROM code parameter.
40h-7Fh	VPD_Data	VPD data filed. Offset 40h is the start address of the VPD data.



# 6.1. Summary of RTL8139D(L) EEPROM Registers

Offset	Name	Type	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0
00h-05h	IDR0 – IDR5	R/W*								
51h	CONFIG0	R		-	=	ı	ı	BS2	BS1	BS0
		$W^*$	Ī	-	-	-	-	-	-	-
52h	CONFIG1	R	LEDS1	LEDS0	DVRLOAD	LWACT	MEMMAP	IOMAP	VPD	PMEN
		$W^*$	LEDS1	LEDS0	DVRLOAD	LWACT	-	1	VPD	PMEN
58h		R	TxFCE	RxFCE	-	-	-	ı		
	1 (CD D) (CD	$W^*$	TxFCE	RxFCE	-	-	-	-		
63H	MSRBMCR	R	Ī	-	Spd_Set	ANE	-	ı	ı	FUDUP
		$W^*$	-	-	Spd_Set	ANE	-	-	-	FUDUP
59h	CONFIG3	R	GNTDel	PARM_EN	Magic	LinkUp	-	-	-	FBtBEn
		$W^*$	-	PARM_EN	Magic	LinkUp	-	-	-	-
5Ah	CONFIG4	R/W*	RxFIFO	AnaOff	LongWF	LWPME	-	LWPTN	-	-
			AutoClr							
78h-7Bh		R/W**		32 bit Read Write						
7Ch-7Fh	TW1_PARM	R/W**	32 bit Read Write							
	TW2_PARM		32 bit Read Write							
80h	PHY2_PARM	R/W**	8 bit Read Write							
<u>D8h</u>	CONFIG5	$R/W^*$	-	-	-	-	-	<u>LDPS</u>	<u>LANWa</u>	PME_ST
									<u>ke</u>	<u>S</u>

<sup>\*</sup> Registers marked with type = 'W\*' can be written only if bits EEM1=EEM0=1.

# 6.2. Summary of EEPROM Power Management Registers

Configuration Space offset	Name	Type	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0
52h	PMC	R	Aux_I_b1	Aux_I_b0	DSI	Reserved	PMECLK		Versio	n
53h		R	PME_D3 <sub>cold</sub>	PME_D3 <sub>ho</sub>	PME_D2	PME_D1	PME_D0	D2	D1	Aux_I_b2
55h	PMCS	R	PME_Status	-	-	-	-	ı	-	PME_En
	R	W	PME_Status	-	-	-	-	1	-	PME_En

<sup>\*\*</sup> Registers marked with type =  $'W^{**'}$  can be written only if bits EEM1=EEM0=1 and CONFIG3<PARM\_EN> = 0.



# 7. PCI Configuration Space Registers

# 7.1. PCI Configuration Space Table

NT	<b>3</b> . T	TT.	B::/5	D://	D1/5	D1/4	DUA	DUA	D*/4	D:40
No.	Name	Type	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0
00h	VID	R	1	1	1	0	1	1	0	0
01h		R	0	0	0	1	0	0	0	0
02h	DID	R	0	0	1	1	1	0	0	1
03h		R	1	0	0	0	0	0	0	1
04h	Command	R	0	PERRSP	0	0	-	BMEN	MEMEN	IOEN
		W	-	PERRSP	-	-	-	BMEN	MEMEN	IOEN
05h		R	0	0	0	0	0	0	FBTBEN	SERREN
		W	-	-	-	-	-	-	-	SERREN
06h	Status	R	FBBC	0	0	NewCap	0	0	0	0
07h		R	DPERR	SSERR	RMABT	RTABT	STABT	DST1	DST0	DPD
		W	DPERR	SSERR	RMABT	RTABT	STABT	-	-	DPD
08h	Revision ID	R	0	0	0	0	0	0	0	0
09h	PIFR	R	0	0	0	0	0	0	0	0
0Ah	SCR	R	0	0	0	0	0	0	0	0
0Bh	BCR	R	0	0	0	0	0	0	1	0
0Ch	CLS	R	0	0	0	0	0	0	0	0
0Dh	LTR	R	LTR7	LTR6	LTR5	LTR4	LTR3	LTP2	LTR1	LTR0
		W	LTR7	LTR6	LTR5	LTR4	LTR3	LTP2	LTR1	LTR0
0Eh	HTR	R	0	0	0	0	0	0	0	0
0Fh	BIST	R	0	0	0	0	0	0	0	0
10h	IOAR	R	0	0	0	0	0	0	0	IOIN
		W	-	-	-	-	-	-	-	-
11h		R/W	IOAR15	IOAR14	IOAR13	IOAR12	IOAR11	IOAR10	IOAR9	IOAR8
12h		R/W	IOAR23	IOAR22	IOAR21	IOAR20	IOAR19	IOAR18	IOAR17	IOAR16
13h		R/W	IOAR31	IOAR30	IOAR29	IOAR28	IOAR27	IOAR26	IOAR25	IOAR24
14h	MEMAR	R	0	0	0	0	0	0	0	MEMIN
		W	ı	-	-	ı	-	ı	-	-
15h		R/W	MEM15	MEM14	MEM13	MEM12	MEM11	MEM10	MEM9	MEM8
16h		R/W	MEM23	MEM22	MEM21	MEM20	MEM19	MEM18	MEM17	MEM16
17h		R/W	MEM31	MEM30	MEM29	MEM28	MEM27	MEM26	MEM25	MEM24
18h-2 Bh					RESE	RVED				
2Ch	SVID	R	SVID7	SVID6	SVID5	SVID4	SVID3	SVID2	SVID1	SVID0
2Dh		R	SVID15	SVID14	SVID13	SVID12	SVID11	SVID10	SVID9	SVID8
2Eh	SMID	R	SMID7	SMID6	SMID5	SMID4	SMID3	SMID2	SMID1	SMID0
2Fh		R	SMID15	SMID14	SMID13	SMID12	SMID11	SMID10	SMID9	SMID8
30h	BMAR	R	0	0	0	0	0	0	0	BROMEN
		W	-	_	-	-	-	-	_	BROMEN
31h		R	BMAR15	BMAR14	BMAR13	BMAR12	BMAR11	0	0	0
		W	BMAR15	BMAR14	BMAR13	BMAR12	BMAR11	_	_	_
32h		R/W	BMAR23	BMAR22	BMAR21	BMAR20	BMAR19	BMAR18	BMAR17	BMAR16
33h		R/W	BMAR31	BMAR30	BMAR29	BMAR28	BMAR27	BMAR26	BMAR25	BMAR24
34h	Cap Ptr	R	0	1	0	1	0	0	0	0
35h-3			· · · · · · · · · · · · · · · · · · ·	<u> </u>	RESE	RVED	<u> </u>	· · · · ·		
Bh					12202					
	I									



No.	Name	Type	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0			
3Ch	ILR	R/W	IRL7	ILR6	ILR5	ILR4	ILR3	ILR2	ILR1	ILR0			
3Dh	IPR	R	0	0	0	0	0	0	0	1			
3Eh	MNGNT	R	0	0	1	0	0	0	0	0			
3Fh	MXLAT	R	R 0 0 1 0 0 0 0										
40h– 4Fh	RESERVED												
50h	PMID R 0 0 0 0 0 0 1												
51h	NextPtr	R	0	0	0	0	0	0	0	0			
52h	PMC	R	Aux I b1	Aux I b0	DSI	Reserved	PMECLK	0	Version	U			
53h	TWIC	R	PME_D3 <sub>cold</sub>		PME D2	PME D1	PME D0	D2	D1	Aux I b2			
54h	PMCSR	R	0	0	0	0	0	0	Power				
0 111	11,10011	W	-	-	-	-	-	-		r State			
55h		R	PME Status	-	-	-	-	-	-	PME En			
		W	PME Status	_	-	-	-	-	-	PME En			
56h-			<u>-</u>		RESE	RVED	•		•	_			
5Fh													
60h	VPDID	R	0	0	0	0	0	0	1	1			
61h	NextPtr	R	0	0	0	0	0	0	0	0			
62h	Flag VPD	R/W	VPDADDR	VPDADDR	VPDADD	VPDADD	VPDADD	VPDADD	VPDADD	VPDADD			
	Address		7	6	R5	R4	R3	R2	R1	R0			
63h		R/W	Flag	VPDADDR	VPDADD	VPDADD	VPDADD	VPDADD	VPDADD	VPDADD			
				14	R13	R12	R11	R10	R9	R8			
64h	VPD Data	R/W	Data7	Data6	Data5	Data4	Data3	Data2	Data1	Data0			
65h		R/W	Data15	Data14	Data13	Data12	Data11	Data10	Data9	Data8			
66h		R/W	Data23	Data22	Data21	Data20	Data19	Data18	Data17	Data16			
67h		R/W	Data31	Data30	Data29	Data28	Data27	Data26	Data25	Data24			
68h-F					RESE	RVED							
Fh													



# 7.2. PCI Configuration Space Functions

The PCI configuration space is intended for configuration, initialization, and catastrophic error handling functions. The functions of the RTL8139D(L)'s configuration space are described below.

**VID:** Vendor ID. This field will default to a value of 10ECh which is Realtek Semiconductor's PCI Vendor ID.

**DID:** Device ID. This field will default to a value of 8139h.

**Command:** The command register is a 16-bit register used to provide coarse control over a device's ability to generate and respond to PCI cycles.

Bit	Symbol	Description
15-10	Symbol	Reserved
	- FDTDEN	
9	FBTBEN	Fast Back-To-Back Enable: Config3 <fbtben>=0:Read as 0. Write operation has no effect. The</fbtben>
		RTL8139D(L) will not generate Fast Back-to-back cycles. When Config3 <fbtben>=1, This</fbtben>
		read/write bit controls whether or not a master can do fast back-to-back transactions to different
		devices. Initialization software will set the bit if all targets are fast back-to-back capable. A value of 1
		means the master is allowed to generate fast back-to-back transaction to different agents. A value of 0
		means fast back-to-back transactions are only allowed to the same agent. This bit's state after RST# is 0.
8	SERREN	<b>System Error Enable:</b> When set to 1, the RTL8139D(L) asserts the SERRB pin when it detects a
		parity error on the address phase (AD<31:0> and CBEB<3:0> ).
7	ADSTEP	Address/Data Stepping: Read as 0, write operation has no effect. The RTL8139D(L) never make
		address/data stepping.
6	PERRSP	<b>Parity Error Response:</b> When set to 1, the RTL8139D(L) will assert the PERRB pin on the detection
		of a data parity error when acting as the target, and will sample the PERRB pin as the master. When set
		to 0, any detected parity error is ignored and the RTL8139D(L) continues normal operation.
		Parity checking is disabled after hardware reset (RSTB).
5	VGASNOO	VGA palette SNOOP: Read as 0, write operation has no effect.
	P	
4	MWIEN	Memory Write and Invalidate cycle Enable: Read as 0, write operation has no effect.
3	SCYCEN	<b>Special Cycle Enable:</b> Read as 0, write operation has no effect. The RTL8139D(L) ignores all special
		cycle operation.
2	BMEN	<b>Bus Master Enable:</b> When set to 1, the RTL8139D(L) is capable of acting as a bus master. When set
		to 0, it is prohibited from acting as a PCI bus master.
		For the normal operation, this bit must be set by the system BIOS.
1	MEMEN	Memory Space Access: When set to 1, the RTL8139D(L) responds to memory space accesses. When
		set to 0, the RTL8139D(L) ignores memory space accesses.
0	IOEN	I/O Space Access: When set to 1, the RTL8139D(L) responds to IO space access. When set to 0, the
		RTL8139D(L) ignores I/O space accesses.



**Status:** The status register is a 16-bit register used to record status information for PCI bus related events. Reads to this register behave normally. Writes are slightly different in that bits can be reset, but not set.

Bit	Symbol	Description
15	DPERR	<b>Detected Parity Error:</b> When set indicates that the RTL8139D(L) detected a parity error, even if parity
		error handling is disabled in command register PERRSP bit.
14	SSERR	Signaled System Error: When set indicates that the RTL8139D(L) asserted the system error pin,
		SERRB. Writing a 1 clears this bit to 0.
13	RMABT	<b>Received Master Abort:</b> When set indicates that the RTL8139D(L) terminated a master transaction
		with master abort. Writing a 1 clears this bit to 0.
12	RTABT	<b>Received Target Abort:</b> When set indicates that the RTL8139D(L) master transaction was terminated
		due to a target abort. Writing a 1 clears this bit to 0.
11	STABT	<b>Signaled Target Abort:</b> Set to 1 whenever the RTL8139D(L) terminates a transaction with target abort.
		Writing a 1 clears this bit to 0.
10-9	DST1-0	<b>Device Select Timing:</b> These bits encode the timing of DEVSELB. They are set to 01b (medium),
		indicating the RTL8139D(L) will assert DEVSELB two clocks after FRAMEB is asserted.
8	DPD	Data Parity error Detected:
		This bit sets when the following conditions are met:
		► The RTL8139D(L) asserts parity error(PERRB pin) or it senses the assertion of PERRB pin by another device.
		► The RTL8139D(L) operates as a bus master for the operation that caused the error.
		► The Command register PERRSP bit is set.
		Writing a 1 clears this bit to 0.
7	FBBC	Fast Back-To-Back Capable: Config3 <fbtben>=0, Read as 0, write operation has no effect.</fbtben>
		Config3 <fbtben>=1, Read as 1.</fbtben>
6	UDF	<b>User Definable Features Supported:</b> Read as 0, write operation has no effect. The RTL8139D(L) does
		not support UDF.
5	66MHz	66 MHz Capable: Read as 0, write operation has no effect. The RTL8139D(L) has no 66MHz
		capability.
4	NewCap	New Capability: Config3 <pmen>=0, Read as 0, write operation has no effect. Config3<pmen>=1,</pmen></pmen>
		Read as 1.
0-3	-	Reserved

#### **RID:** Revision ID Register

The Revision ID register is an 8-bit register that specifies the RTL8139D(L) controller revision number.

#### PIFR: Programming Interface Register

The programming interface register is an 8-bit register that identifies the programming interface of the RTL8139D(L) controller. Because the PCI version 2.1 specification does not define any specific value for network devices, PIFR = 00h.

#### **SCR:** Sub-Class Register

The Sub-class register is an 8-bit register that identifies the function of the RTL8139D(L). SCR = 00h indicates that the RTL8139D(L) is an Ethernet controller.

#### **BCR:** Base-Class Register

The Base-class register is an 8-bit register that broadly classifies the function of the RTL8139D(L). BCR = 02h indicates that the RTL8139D(L) is a network controller.

#### **CLS:** Cache Line Size

Reads will return a 0, writes are ignored.

#### LTR: Latency Timer Register

Specifies, in units of PCI bus clocks, the value of the latency timer of the RTL8139D(L).

When the RTL8139D(L) asserts FRAMEB, it enables its latency timer to count. If the RTL8139D(L) deasserts FRAMEB prior to count expiration, the content of the latency timer is ignored. Otherwise,



after the count expires, the RTL8139D(L) initiates transaction termination as soon as its GNTB is deasserted. Software is able to read or write, and the default value is 00H.

**HTR:** Header Type Register

Reads will return a 0, writes are ignored.

**BIST:** Built-in Self Test

Reads will return a 0, writes are ignored.

**IOAR:** This register specifies the BASE IO address which is required to build an address map during configuration. It also specifies the number of bytes required as well as an indication that it can be mapped into IO space.

Bit	Symbol	Description
31-8	IOAR31-8	<b>BASE IO Address:</b> This is set by software to the Base IO address for the operational register map.
7-2	IOSIZE	<b>Size Indication:</b> Read back as 0. This allows the PCI bridge to determine that the RTL8139D(L)
		requires 256 bytes of IO space.
1	-	Reserved
0	IOIN	<b>IO Space Indicator:</b> Read only. Set to 1 by the RTL8139D(L) to indicate that it is capable of being
		mapped into IO space.

**MEMAR:** This register specifies the base memory address for memory accesses to the RTL8139D(L) operational registers. This register must be initialized prior to accessing any RTL8139D(L)'s register with memory access.

Bit	Symbol	Description
31-8	MEM31-8	<b>Base Memory Address:</b> This is set by software to the base address for the operational register map.
7-4	MEMSIZE	Memory Size: These bits return 0, which indicates that the RTL8139D(L) requires 256 bytes of
		Memory Space.
3	MEMPF	<b>Memory Prefetchable:</b> Read only. Set to 0 by the RTL8139D(L).
2-1	MEMLOC	Memory Location Select: Read only. Set to 0 by the RTL8139D(L). This indicates that the base
		register is 32-bit wide and can be placed anywhere in the 32-bit memory space.
0	MEMIN	<b>Memory Space Indicator:</b> Read only. Set to 0 by the RTL8139D(L) to indicate that it is capable of
		being mapped into memory space.

**SVID:** Subsystem Vendor ID. This field will be set to a value corresponding to PCI Subsystem Vendor ID in the external EEPROM. If there is no EEPROM, this field will default to a value of 10ECh which is Realtek Semiconductor's PCI Subsystem Vendor ID.

**SMID:** Subsystem ID. This field will be set to value corresponding to PCI Subsystem ID in the external EEPROM. If there is no EEPROM, this field will default to a value of 8139h.

**BMAR:** This register specifies the base memory address for memory accesses to the Rtl8139D(L) operational registers. This register must be initialized prior to accessing any Rtl8139D(L) 's register with memory access.



Bit	Symbol	Description
31-18	BMAR31-18	Boot ROM Base Address
17-11	ROMSIZE	These bits indicate how many Boot ROM spaces to be supported.  The Relationship between Config 0 <bs2:0> and BMAR17-11 is the following:  BS2 BS1 BS0 Description  0 0 0 No Boot ROM, BROMEN=0 (R)  0 0 1 8K Boot ROM, BROMEN (R/W), BMAR12-11 = 0 (R), BMAR17-13 (R/W)  0 1 0 16K Boot ROM, BROMEN (R/W), BMAR13-11 = 0 (R), BMAR17-14 (R/W)  0 1 1 32K Boot ROM, BROMEN (R/W), BMAR14-11 = 0 (R), BMAR17-15 (R/W)  1 0 0 64K Boot ROM, BROMEN (R/W), BMAR15-11 = 0 (R), BMAR17-16 (R/W)  1 1 1 28K Boot ROM, BROMEN(R/W), BMAR16-11=0 (R), BMAR17 (R/W)  1 1 0 unused</bs2:0>
10-1	-	1 1 1 unused Reserved (read back 0)
0	BROMEN	Boot ROM Enable: This is used by the PCI BIOS to enable accesses to Boot ROM.

#### **ILR:** Interrupt Line Register

The Interrupt Line Register is an 8-bit register used to communicate with the routing of the interrupt. It is written by the POST software to set interrupt line for the RTL8139D(L).

#### **IPR:** Interrupt Pin Register

The Interrupt Pin register is an 8-bit register indicating the interrupt pin used by the RTL8139D(L). The RTL8139D(L) uses INTA interrupt pin. Read only. IPR = 01H.

#### MNGNT: Minimum Grant Timer: Read only

Specifies how long a burst period the RTL8139D(L) needs at 33 MHz clock rate in units of 1/4 microsecond. This field will be set to a value from the external EEPROM. If there is no EEPROM, this field will default to a value of 20h

#### MXLAT: Maximum Latency Timer: Read only

Specifies how often the RTL8139D(L) needs to gain access to the PCI bus in unit of 1/4 microsecond. This field will be set to a value from the external EEPROM. If there is no EEPROM, this field will default to a value of 20h.



# 7.3. Default Values after Power-on (RSTB Asserted) PCI Configuration Space Table

O6h	No.	Name	Type	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0
O2h	00h	VID	R	1	1	1	0	1	1	0	0
O3h	01h		R	0	0	0	1	0	0	0	0
O-9	02h	DID	R	0	0	1	1	1	0	0	1
No.   Perror   Perr	03h		R	1	0	0	0	0	0	0	1
OSh	04h	Command	R	0	0	0	0	0	0	0	0
Note				-	PERRSP	-	-	=	BMEN	MEMEN	IOEN
O6h	05h			0	0	0	0	0	0	0	_
O7h				-		-					SERREN
Note		Status					NewCap				
08h         Revision ID         R         0         <	07h	_							0	1	_
O9h						RMABT				1	
OAh   SCR   R											
OBh											
OCh         CLS         R         0 <td></td>											
ODh											
W											
0Eh         HTR         R         0 <td>0Dh</td> <td>LTR</td> <td></td> <td></td> <td></td> <td>-</td> <td>-</td> <td></td> <td></td> <td></td> <td>_</td>	0Dh	LTR				-	-				_
OFh         BIST         R         0 <td></td> <td></td> <td></td> <td></td> <td></td> <td>LTR5</td> <td>LTR4</td> <td>LTR3</td> <td></td> <td>LTR1</td> <td></td>						LTR5	LTR4	LTR3		LTR1	
10h						0				0	
11h						0					0
12h		IOAR									_
13h											
14h		_									
Solution   Solution											
R/W   O   O   O   O   O   O   O   O   O		MEMAR									
17h											
18h		-									
2Bh			R/W	0		· ·	_	0	0	0	0
SVID   R	18h					RESERVE	D(ALL 0)				
SVID   R	2D1										
SMID   R   O   O   O   I   O   O   O   I		CMD	D	1	1	1	0	1	1	0	0
SMID   R		SVID									
Part		CMID									
Sumarrow		SMID									
W   -   -   -   -   -   -   BROMEN		DMAD									
R   O   O   O   O   O   O   O   O   O	30n	BMAK			-						_
W   BMAR15   BMAR14   BMAR13   BMAR12   BMAR11   -   -   -   -       32h	211	-									
S2h	3111	-									
33h         R/W         0         0         0         0         0         0         0           34h         Cap-Ptr         R         Ptr7         Ptr6         Ptr5         Ptr4         Ptr3         Ptr2         Ptr1         Ptr0           35h         I         RESERVED(ALL 0)         RESERVED(ALL 0)         I	226	-									
34h Cap-Ptr R Ptr7 Ptr6 Ptr5 Ptr4 Ptr3 Ptr2 Ptr1 Ptr0 35h RESERVED(ALL 0)		<del> </del>									
35h RESERVED(ALL 0)		Can Dir									
		Cap-Pii	N.	ru/				гиз	FUZ	FUI	ruv
201	J.J.II 					KESEK VE.	D(ALL U)				
) 150 I	3Bh										



No.	Name	Type	Bit7	Bit6	Bit5	Bit4	Bit3	Bit2	Bit1	Bit0
3Ch	ILR	R/W	0	0	0	0	0	0	0	0
3Dh	IPR	R	0	0	0	0	0	0	0	1
3Eh	MNGNT	R	0	0	1	0	0	0	0	0
3Fh	MXLAT	R	0	0	1	0	0	0	0	0
40h			RESERVED(ALL 0)							
	-									
FFh										

## 7.4. PCI Power Management Functions

The RTL8139D(L) complies with ACPI (Rev 1.1), PCI Power Management (Rev 1.1), and Device Class Power Management Reference Specification (V1.0a), such as to support OS Directed Power Management (OSPM) environment. To support this, the RTL8139D(L) provides the following capabilities:

- ➤ The RTL8139D(L) can monitor the network for a Wakeup Frame, a Magic Packet, or a Link Change, and notify the system via PME# when such a packet or event arrives. Then, the whole system can restore to working state to process the incoming jobs.
- The RTL8139D(L) can be isolated from the PCI bus automatically with the auxiliary power circuit when the PCI bus is in B3 state, i.e. the power on the PCI bus is removed. When the motherboard includes a built-in RTL8139D(L) single-chip fast Ethernet controller, the RTL8139D(L) can be disabled when needed by pulling the isolate pin low to 0V.

When the RTL8139D(L) is in power down mode (D1  $\sim$  D3),

- ♦ The Rx state machine is stopped, and the RTL8139D(L) keeps monitoring the network for wakeup event such Magic Packet, Wakeup Frame, and/or Link Change, in order to wake up the system. When in power down mode, the RTL8139D(L) will not reflect the status of any incoming packet in the ISR register and will not receive any packet into Rx FIFO.
- ♦ The FIFO status and the packets which are already received into Rx FIFO before entering into power down mode, are kept by the RTL8139D(L) during power down mode
- ◆ The transmission is stopped. The action of PCI bus master mode is stopped, too. The Tx FIFO is kept.
- ♦ After restoring to a D0 state, the PCI bus master mode continues to transfer the data, which is not yet moved into Tx FIFO from the last break. The packet that was not transmitted completely last time is transmitted again.



D3cold\_support\_PME bit(bit15, PMC register) & Aux\_I\_b2:0 (bit8:6, PMC register) in PCI configuration space.

If 9346 D3cold\_support\_PME bit(bit15, PMC) = 1, the above 4 bits depend on the existence of Aux power.

If 9346 D3cold\_support\_PME bit(bit15, PMC) = 0, the above 4 bits are all 0's.

Ex.:

- 1. If 9346 D3c support PME = 1,
  - Aux. power exists, then PMC in PCI config space is the same as 9346 PMC, i.e. if 9346 PMC = C2 F7, then PCI PMC = C2 F7.
  - Aux. power is absent, then PMC in PCI config space is the same as 9346 PMC except the above 4 bits are all 0's. I.e. if 9346 PMC = C2 F7, the PCI PMC = 02 76.
    - \* In this case, if wakeup support is desired when the main power is off, it is suggested that the 9346 PMC be set to: C2 F7 (RT 9346 default value). It is not recommended to set the D0 support PME bit to "1".
- 2. If 9346 D3c support PME = 0,
  - Aux. power exists, then PMC in PCI config space is the same as 9346 PMC. I.e. if 9346 PMC = C2 77, then PCI PMC = C2 77.
  - Aux. power is absent, then PMC in PCI config space is the same as 9346 PMC except the above 4 bits are all 0's. I.e. if 9346 PMC = C2 77, the PCI PMC = 02 76.
    - \* In this case, if wakeup support is not desired when the main power is off, it is suggested that the 9346 PMC to be 02 76. It is not recommended to set the D0 support PME bit to "1".

Link Wakeup occurs only when the following conditions are approved,

- ♦ The LinkUp bit (CONFIG3#4) is set to 1, the PMEn bit (CONFIG1#0) is set to 1, and the RTL8139D(L) is in isolation state, or the PME# can be asserted in current power state.
- ♦ The Link status is re-established.

Magic Packet Wakeup occurs only when the following conditions are met:

- The destination address of the received Magic Packet matches.
- ♦ The received Magic Packet does not contain CRC error.
- ◆ The Magic bit (CONFIG3#5) is set to 1, the PMEn bit (CONFIG1#0) is set to 1, and the RTL8139D(L) is in isolation state, or the PME# can be asserted in current power state.
- ◆ The Magic Packet pattern matches, i.e. 6 \* FFh + MISC(can be none)+ 16 \* DID(Destination ID) in any part of a valid (Fast) Ethernet packet.

Wakeup Frame event occurs only when the following conditions are met:

- The destination address of the received Wakeup Frame matches.
- ♦ The received Wakeup Frame does not contain a CRC error.
- ◆ The PMEn bit (CONFIG1#0) is set to 1.
- ◆ The 8-bit CRC\* (or 16-bit CRC) of the received Wakeup Frame matches with the 8-bit CRC\* (or 16-bit CRC) of the sample Wakeup Frame pattern received from the local machine's OS.



◆ The *last masked byte*\*\* of the received Wakeup Frame matches with the *last masked byte*\*\* of the sample Wakeup Frame pattern provided by the local machine's OS. (In Long Wakeup Frame mode, the last masked byte field is replaced with the high byte of the 16-bit CRC.)

#### • 8-bit CRC:

This 8-bit CRC logic is use to generate an 8-bit CRC from the masked bytes of the received Wakeup Frame packet within offset 12 to 75. Software should calculate the 8-bit Power Management CRC for each specific sample wakeup frame and store the calculated CRC in the corresponding CRC register for the RTL8139D(L) to check if there is Wakeup Frame packet coming in.

#### • 16-bit CRC: (Long Wakeup Frame mode, the mask bytes cover from offset 0 to 127)

Long Wakeup Frame: The RTL8139D(L) also supports 3 long Wakeup Frames. If the range of mask bytes of the sample Wakeup Frame, passed down by the OS to the driver, exceeds the range from offset 12 to 75, the related registers of wakeup frame 2 and 3 can be merged to support one long wakeup frame by setting the LongWF (bit0, CONFIG4). Thus, the range of effective mask bytes extends from offset 0 to 127. The low byte and high byte of calculated 16-bit CRC should be put into register CRC2 and LSBCRC2 respectively. The mask bytes (16 bytes) should be store to register Wakeup2 and Wakeup3. The CRC3 and LSBCRC3 have no meaning in this case and should be reset to 0. So as the long Wakeup Frame pairs, wakeup frame 4 and 5, wakeup frame 6 and 7. The CRC5, CRC7, LSBCRC5, and LSBCRC7 have no meaning in this case and should be reset to 0, if the RTL8139D(L) is set to support long Wakeup Frame. In this case, the RTL8139D(L) support 5 wakeup frames, that are 2 normal wakeup frames and 3 long wakeup frames.

#### \*\* last masked byte:

The last byte of the masked bytes of the received Wakeup Frame packet within offset 12 to 75 (in 8-bit CRC mode) should matches with the last byte of the masked bytes of the sample Wakeup Frame provided by the local machine's OS.

The PME# signal is asserted only when the following are approved,

- ◆ The PMEn bit (bit0, CONFIG1) is set to 1.
- ◆ The PME En bit (bit8, PMCSR) in PCI Configuration Space is set to 1.
- ◆ The RTL8139D(L) may assert PME# in current power state, or the RTL8139D(L) is in isolation state. Refer to PME Support(bit15-11) of the PMC register in PCI Configuration Space.
- Magic Packet, LinkUp, or Wakeup Frame has occurred.
  - \* Writing a 1 to the PME\_Status (bit15) of PMCSR register in the PCI Configuration Space will clear this bit and cause the RTL8139D(L) to stop asserting a PME# (if enabled).

When the RTL8139D(L) is in power down mode, ex. D1-D3, the IO, MEM, and Boot ROM space are all disabled. After RST# asserted, the power state must be changed to D0 if the original power state is D3<sub>cold</sub>. There is no hardware enforced delays at RTL8139D(L)'s power state. When in ACPI mode, the RTL8139D(L) does not support PME from D0 (owing to the setting of PMC register. This setting comes from EEPROM).



The RTL8139D(L) also supports LAN WAKE-UP function. The LWAKE pin is used to notify the motherboard to execute wake-up process whenever the RTL8139D(L) receives a wakeup event, such as Magic Packet.

The LWAKE signal is asserted according the following setting.

- ◆ LWPME bit (bit4, CONFIG4):
  - 0: The LWAKE is asserted whenever there is wakeup event occurs.
  - 1: The LWAKE can only be asserted when the PMEB is asserted and the ISOLATEB is low.
- ◆ Bit1 of DELAY byte(offset 1Fh, EEPROM):
  - 0: LWAKE signal is disabled.
  - 1: LWAKE signal is enabled


#### VPD (Vital Product Data)

Bit 31 of the Vital Product Data (VPD) is used to issue VPD read/write commands, and is also a flag used to indicate whether the transfer of data between the VPD data register and the 93C46 is completed or not.

- 1. Write VPD register: (write data to 93C46)
  Write the flag bit to a one (at the same time the VPD address is written). When the flag bit is set to zero by the RTL8139D(L), the VPD data (all 4 bytes) has been transferred from the VPD data register to 93C46.
- 2. Read VPD register: (read data from 93C46)
  Write the flag bit to a zero at the same time the VPD address is written). When the flag bit is set to one by the RTL8139D(L), the VPD data (all 4 bytes) has been transferred from 93C46 to the VPD data register.



# 8. Block Diagram



Single Chip Multifunction 10/100 Ethernet Controller w/Power Management



# 9. Functional Description

# 9.1. Transmit Operation

The host CPU initiates a transmit by storing an entire packet of data in one of the descriptors in the main memory. When the entire packet has been transferred to the Tx buffer, the RTL8139D(L) is instructed to move the data from the Tx buffer to the internal transmit FIFO in PCI bus master mode. When the transmit FIFO contains a complete packet or is filled to the programmed threshold level, the RTL8139D(L) begins packet transmission.

# 9.2. Receive Operation

The incoming packet is placed in the RTL8139D(L)'s Rx FIFO. Concurrently, the RTL8139D(L) performs address filtering of multicast packets according to its hash algorithms. When the amount of data in the Rx FIFO reaches the level defined in the Receive Configuration Register, the RTL8139D(L) requests the PCI bus to begin transferring the data to the Rx buffer in PCI bus master mode.

## 9.3. Base Line Wander Compensation

The 8139D(L) is ANSI TP-PMD compliant and supports input and Base Line Wander (BLW) compensation in 100Base-TX mode. The 8139D(L) does not require external attenuation circuitry at its receive inputs, RD+/-. It accepts TP-PMD compliant waveforms directly, requiring only a  $100\Omega$  termination and a 1:1 transformer.

BLW is the change in the average DC content, over time, of an AC coupled digital transmission over a given transmission medium. BLW is a result from the interaction between the low frequency components of a transmitted bit stream and the frequency response of the AC coupling component(s) within the transmission system. If the low frequency content of the digital bit stream goes below the low frequency pole of the AC coupling transformers, then the droop characteristics of the transformers will dominate, resulting in potentially serious BLW. If BLW is not compensated, packet loss can occur.

## 9.4. Line Quality Monitor

The line quality monitor function is available in 100Base-TX mode. It is possible to determine the amount of Equalization being used by accessing certain test registers with the DSP engine. This provides a crude indication of connected cable length. This function allows for a quick and simple verification of the line quality in that any significant deviation from an expected register value (based on a known cable length) would indicate that the signal quality has deviated from the expected nominal case.



## 9.5. Clock Recovery Module

The Clock Recovery Module (CRM) is supported in 100Base-TX mode. The CRM accepts 125Mbps MLT3 data from the equalizer. The DPLL locks onto the 125Mbps data stream and extracts a 125MHz recovered clock. The extracted and synchronized clock and data are used as required by the synchronous receive operations.

## 9.6. Loopback Operation

Loopback mode is normally used to verify that the logic operations up to the Ethernet cable function correctly. In loopback mode for 100Mbps, the RTL8139D(L) takes frames from the transmit descriptor and transmits them up to internal Twister logic.

## 9.7. Tx Encapsulation

While operating in 100Base-TX mode, the RTL8139D(L) encapsulates the frames that it transmits according to the 4B/5B code-groups table. The changes of the original packet data are listed as follows:

- 1. The first byte of the preamble in the MAC frame is replaced with the JK symbol pair.
- 2. After the CRC, the TR symbol pair is inserted.

### 9.8. Collision

If the RTL8139D(L) is not in the full-duplex mode, a collision event occurs when the receive input is not idle while the RTL8139D(L) transmits. If the collision was detected during the preamble transmission, the jam pattern is transmitted after completing the preamble (including the JK symbol pair).



# 9.9. Rx Decapsulation

The RTL8139D(L) continuously monitors the network when reception is enabled. When activity is recognized it starts to process the incoming data.

After detecting receive activity on the line, the RTL8139D(L) starts to process the preamble bytes based on the mode of operation.

While operating in 100Base-Tx mode, the RTL8139D(L) expects the frame to start with the symbol pair JK in the first byte of the 8-byte preamble.

The RTL8139D(L) checks the CRC bytes and checks if the packet data ends with the TR symbol pair, if not, the RTL8139D(L) reports an CRC error RSR.

The RTL8139D(L) reports a RSR<CRC> error in any of the following cases:

- 1. In 100Base-Tx mode, one of the following occurs:
- a. An invalid symbol (4B/5B Table) is received in the middle of the frame. RSR<ISE> bit also sets.
- b. The frame does not end with the TR symbol pair.

#### 9.10. Flow Control

The RTL8139D(L) supports IEEE802.3X flow control to improve performance in full-duplex mode. It detects PAUSE packet to achieve flow control task.

#### 9.10.1. Control Frame Transmission

When the RTL8139D(L) detects that its free receive buffer is less than 3K bytes, it sends a **PAUSE packet** with pause\_time(=FFFFh) to inform the source station to stop transmission for the specified period of time. After the driver has processed the packets in the receive buffer and updated the boundary pointer, the RTL8139D(L) sends the other **PAUSE packet with pause\_time(=0000h)** to wake up the source station to restart transmission

## 9.10.2. Control Frame Reception

The RTL8139D(L) enters a back off state for a specified period of time when it receives a valid **PAUSE packet with pause\_time(=n)**. If the PAUSE packet is received while the RTL8139D(L) is transmitting, the RTL8139D(L) starts to back off after current transmission completes. The RTL8139D(L) is free to transmit the next packets when it receives a valid **PAUSE** packet with pause\_time(=0000h) or the backoff timer(=n\*512 bit time) elapses.

Note: The PAUSE operation cannot be used to inhibit transmission of MAC Control frames (e.g. PAUSE packet). The N-way flow control capability can be disabled, please refer to Section 6, EEPROM (93C46) Contents for a detailed description.




# 9.11. LED Functions

# **9.11.1. 10/100Mbps Link Monitor**

The Link Monitor senses the link integrity or if a station is down.


# 9.11.2. LED\_RX

In 10/100 Mbps mode, the LED function is the same as the RTL8139C(L).






# 9.11.3. LED\_TX




# 9.11.4. LED\_TX+LED\_RX





# 10. Application Diagram





# 11. Electrical Characteristics

# 11.1. Temperature Limit Ratings

Parameter	Minimum	Maximum	Units
Storage temperature	-55	+125	°C
Operating temperature	0	70	°C

## 11.2. DC Characteristics

11.2.1. Supply Voltage Vcc = 3.0V min. to 3.6V max.

	supply volume vee to visit minute to the visit make							
Symbol	Parameter	Conditions	Minimum	Maximum	Units			
$v_{OH}$	Minimum High Level Output Voltage	I <sub>OH=</sub> -8mA	0.9 * Vcc	Vcc	V			
$v_{OL}$	Maximum Low Level Output Voltage	I <sub>OL</sub> = 8mA		0.1 * Vcc	V			
$v_{\mathrm{IH}}$	Minimum High Level Input Voltage		0.5 * Vcc	Vcc+0.5	V			
$v_{IL}$	Maximum Low Level Input Voltage		-0.5	0.3 * Vcc	V			
I <sub>IN</sub>	Input Current	V <sub>IN=</sub> V <sub>CC</sub> or	-1.0	1.0	uA			
		GND						
$I_{OZ}$	Tri-State Output Leakage Current	V <sub>OUT=</sub> V <sub>CC or</sub>	-10	10	uA			
		GND						
I <sub>CC</sub>	Average Operating Supply Current	I <sub>OUT</sub> =0mA,		330	mA			

11.2.2. Supply Voltage Vdd25 = 2.3V min. to 2.7V max.


Symbol	Parameter	Conditions	Minimum	Maximum	Units
$v_{OH}$	Minimum High Level Output Voltage	I <sub>OH</sub> = -8mA	0.9 * Vdd25	Vdd25	V
$v_{OL}$	Maximum Low Level Output Voltage	I <sub>OL</sub> = 8mA		0.1 * Vdd25	V
$v_{IH}$	Minimum High Level Input Voltage		0.5 * Vdd25	Vdd25+0.5	V
$v_{\mathrm{IL}}$	Maximum Low Level Input Voltage		-0.5	0.3 * Vdd25	V
I <sub>IN</sub>	Input Current	V <sub>IN=</sub> V <sub>dd25 or</sub> GND	-1.0	1.0	uA
I <sub>OZ</sub>	Tri-State Output Leakage Current	V <sub>OUT=</sub> V <sub>dd25</sub> or GND	-10	10	uA
I <sub>dd25</sub>	Average Operating Supply Current	I <sub>OUT</sub> =0mA,		40	mA




# 11.3. AC Characteristics

# 11.3.1. PCI Bus Operation Timing

## **Target Read**




## **Target Write**






## **Configuration Read**




# **Configuration Write**






## **BUS Arbitration**




## **Memory Read**






## **Memory Write**




# **Target Initiated Termination - Retry**






# **Target Initiated Termination - Disconnect**





## **Target Initiated Termination - Abort**





## **Master Initiated Termination – Abort**








# 12. Mechanical Dimensions

# 12.1. QFP



N	otos
IN	otes


Symbol	Dime	nsion ii	n mil	Dimension in mm			
	Min	Typical	Max	Min	Typical	Max	
A	106.3	118.1	129.9	2.70	3.00	3.30	
<b>A</b> 1	4.3	20.1	35.8	0.11	0.51	0.91	
A <sub>2</sub>	102.4	112.2	122.0	2.60	2.85	3.10	
b	7.1	11.8	16.5	0.18	0.30	0.42	
c	1.6	5.9	10.2	0.04	0.15	0.26	
D	541.3	551.2	561.0	13.75	14.00	14.25	
E	777.6	787.4	797.2	19.75	20.00	20.25	
е	19.7	25.6	31.5	0.50	0.65	0.80	
$\mathbf{H}_{\mathrm{D}}$	726.4	740.2	753.9	18.45	18.80	19.15	
HE	962.6	976.4	990.2	24.45	24.80	25.15	
L	39.4	47.2	55.1	1.00	1.20	1.40	
$\mathbf{L}_1$	88.6	94.5	104.3	2.25	2.40	2.65	
Y	-	-	3.9	-	-	0.10	
θ	0°	_	12°	0°	_	12°	


- 1. Dimension D & E do not include interlead flash.
- 2. Dimension b does not include dambar protrusion/intrusion.
- 3. Controlling dimension: Millimeter
- 4.General appearance spec. should be based on final visual inspection spec.


TITLE: 100L QFP (14x20 mm**2) FOOTPRINT 4.8 mm							
	PACKAGE OUTLINE DRAWING						
	LEADFRAME MATERIAL:						
APPROVE	DWG NO.						
	REV NO.						
	SCALE						
CHECK	Ricardo Chen	DATE					
SHT NO. 1 OF							
REALTEK SEMICONDUCTOR CORP.							



# 12.2. LQFP







SECTION B-B

#### Notes:

- 1.To be determined at seating plane -c-
- 2.Dimensions D<sub>1</sub> and E<sub>1</sub> do not include mold protrusion. D<sub>1</sub> and E<sub>1</sub> are maximum plastic body size dimensions including mold mismatch.
- 3. Dimension b does not include dambar protrusion.

  Dambar can not be located on the lower radius of the foot.
- 4.Exact shape of each corner is optional.
- 5. These dimensions apply to the flat section of the lead between 0.10 mm and 0.25 mm from the lead tip.
- 6. A<sub>1</sub> is defined as the distance from the seating plane to the lowest point of the package body.
- 7. Controlling dimension: millimeter.
- 8. Reference document: JEDEC MS-026, BED.

8. Reference document: JEDEC MS-026, BED.							
TI	TITLE: 100LD LQFP ( 14x14x1.4mm)						
PACKAGE	OUTLINE DE	RAWING, FOOT	ΓPRINT 2.0mm				
	LEADFRAME MATERIAL:						
APPROVE	DOC. NO.						
		VERSION	1				
	PAGE OF						
CHECK	CHECK DWG NO. LQ100 - P1						
DATE							
REA	REALTEK SEMICONDUCTOR CORP.						

Symbol	Dime	nsion ii	n inch	Dime	nsion ii	n mm	
	Min	Nom	Max	Min	Nom	Max	
A	-	-	0.067	-	-	1.70	
<b>A</b> 1	0.000	0.004	0.008	0.00	0.1	0.20	
A <sub>2</sub>	0.051	0.055	0.059	1.30	1.40	1.50	
b	0.006	0.009	0.011	0.15	0.22	0.29	
b1	0.006	0.008	0.010	0.15	0.20	0.25	
c	0.004	ı	0.008	0.09	-	0.20	
C1	0.004	-	0.006	0.09	-	0.16	
D	0.630 BSC			16.00 BSC			
<b>D</b> 1	0.	.551 BS	С	14.00 BSC			
E	0.	.630 BS	С	16.00 BSC			
$\mathbf{E_1}$	0.	.551 BS	С	14.00 BSC			
е	0.	.020 BS	С	0.50 BSC			
L	0.016	0.024	0.031	0.40	0.60	0.80	
$\mathbf{L}_1$	0.	.039 RE	F	1.00 REF			
θ	0°	3.5°	9°	0°	3.5°	9°	
θ1	0°	-		0°			
θ 2	12°TYP			12°TYP			
θ3	12°TYP			12°TYP			



# 13. Ordering Information

**Table 1. Ordering Information** 

Part Number	Package	Status
RTL8139D	QFP-100	
RTL8139DL	LQFP-100	
RTL8139D-LF	RTL8139D with Lead (Pb)-Free package	
RTL8139DL-LF	RTL8139DL with Lead (Pb)-Free package	
RTL8139D-GR	RTL8139D with 'Green' package	
RTL8139DL-GR	RTL8139DL with 'Green' package	

Note: See page 2 and page 3 for package identification.

Realtek Semiconductor Corp. Headquarters

No. 2, Industry East Road IX, Science-based Industrial Park, Hsinchu, 300, Taiwan, R.O.C. Tel: 886-3-5780211 Fax: 886-3-5774713 www.realtek.com.tw



Компания «ЭлектроПласт» предлагает заключение долгосрочных отношений при поставках импортных электронных компонентов на взаимовыгодных условиях!

#### Наши преимущества:

- Оперативные поставки широкого спектра электронных компонентов отечественного и импортного производства напрямую от производителей и с крупнейших мировых складов:
- Поставка более 17-ти миллионов наименований электронных компонентов;
- Поставка сложных, дефицитных, либо снятых с производства позиций;
- Оперативные сроки поставки под заказ (от 5 рабочих дней);
- Экспресс доставка в любую точку России;
- Техническая поддержка проекта, помощь в подборе аналогов, поставка прототипов;
- Система менеджмента качества сертифицирована по Международному стандарту ISO 9001:
- Лицензия ФСБ на осуществление работ с использованием сведений, составляющих государственную тайну;
- Поставка специализированных компонентов (Xilinx, Altera, Analog Devices, Intersil, Interpoint, Microsemi, Aeroflex, Peregrine, Syfer, Eurofarad, Texas Instrument, Miteq, Cobham, E2V, MA-COM, Hittite, Mini-Circuits, General Dynamics и др.);

Помимо этого, одним из направлений компании «ЭлектроПласт» является направление «Источники питания». Мы предлагаем Вам помощь Конструкторского отдела:

- Подбор оптимального решения, техническое обоснование при выборе компонента;
- Подбор аналогов;
- Консультации по применению компонента;
- Поставка образцов и прототипов;
- Техническая поддержка проекта;
- Защита от снятия компонента с производства.



#### Как с нами связаться

**Телефон:** 8 (812) 309 58 32 (многоканальный)

Факс: 8 (812) 320-02-42

Электронная почта: <u>org@eplast1.ru</u>

Адрес: 198099, г. Санкт-Петербург, ул. Калинина,

дом 2, корпус 4, литера А.